

N6893626Q5020 - HVAC Replacement

Questions & Answers

1/15/26

1. Is this project tax exempt? If so, will a tax exemption certificate be provided? **Not tax exempt.**
2. Will there be a site visit to review existing conditions? **A site visit can be arranged.**
3. Are the engineered construction drawings in Section J – Part 6 the only governing drawings, or are there as-builts or elevator manufacturer documents that must also be followed? **The engineered construction drawings in Section J – Part 6 the only governing drawings**
4. Is removal and disposal of the existing HEVC system included in the contractor's scope, including hydronic piping and controls? **Yes. Please see the M-1 drawing for demo scope. Existing thermostat shall be replaced with a new 7-day programmable thermostat with locking cover.**
5. Does the scope include testing and commissioning of the elevator system after HVAC replacement, or only HVAC TAB? **Only HVAC TAB**
6. Are control integration required with any existing Building Automation System (BAS), or is the unit stand-alone? **Stand Alone**
7. Who is the controls contractor at the facility? **There is no control contractor at the facility. Please see the drawing M-1, Key Notes 3. KTR to provide 7 days programmable thermostat with locking cover.**
8. What is the Period of Performance for this project? **90 days.**
9. Is on-base staging or temporary storage space available? **There is space for a laydown area, which can be discussed more at the Pre-Con.**
10. Are there any hazardous materials used on the mechanical piping or hangers? **Hazardous materials in piping or hangers are not expected. If ACMS or LCP found or disturbed during the construction, comply with UFGS specifications Section 02 82 16.00 20 Engineering Control of Asbestos Containing Materials and Section 02 83 13.00 20 Lead in Construction.**
11. Will Civil Engineering utilize Procore as a project management tool? **No**
12. Can you provide the model and serial number of the existing unit?
Model # GRT-1-1225-MAO-HWEVC-2T-MSD
Serial # 1154-0393-182
13. Is the Buy-American Act applicable to this contract? **Yes**
14. Are there liquidated damages associated with this contract? **No**
15. Does a smoke detector need to be installed in the ductwork of the new unit? **No**
16. Is the contractor responsible for roof patching? **Yes. Please see the drawing M-1, General Demolition Notes 5.**
17. Could you please confirm what type of solicitation this is? (Request for Quotes (RFQ), Request for Proposals (RFP), etc.)
This is a request for quote
18. Is this being solicited under FAR 13 (SAP), or FAR 15, or other?
This is being solicited following FAR Part 13 and 36