

CANTONMENT GROUND MAINTENANCE SERVICES
PERFORMANCE WORK STATEMENT (PWS)

Fort Rucker, Alabama

August 2025

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

Table of Contents

1.0	General.....	1
1.1	Description of Services/Introduction.	1
1.2	Background.....	1
1.3	Objectives.	2
1.4	Scope.....	2
1.5	Period of Performance (PoP).	3
1.6	Traffic Flow.	3
1.7	Restoration of Real Property Damage.....	3
1.8	General Information.	3
1.8.1	Place of Performance.....	3
1.8.2	Recognized Holidays.	3
1.8.3	Hours of Operation.....	4
1.8.4	Installation Closures.....	4
1.8.5	Emergency Delays.....	5
1.8.6	Unforeseen Closures of Service Areas.	5
1.8.7	Type of Contract.	5
1.8.8	Security Requirements and Training.	5
1.8.9	Local Health Protection Conditions	7
1.8.10	Key Control.	7
1.8.11	Lost Keys.	7
1.8.12	Prohibited use of Government provided keys or key cards.....	8
1.8.13	Post Award Conference/Periodic Progress Meetings.	8
1.9	Government Roles and Responsibilities.	9
1.9.1	Contracting Officer (KO).....	9
1.9.2	Contracting Officer’s Representative (COR).	9
1.9.3	COR Authority.....	9
1.9.4	COR or Designated Government Representative Functions.	10
1.10	Specific Contractor Requirements, Roles and Responsibilities.....	10
1.10.1	U.S. Residency.	10
1.10.2	Contractor Hiring Restrictions.	10
1.10.3	Contractor Identification.	10
1.10.4	Standards of Conduct.	11

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

1.10.5 Contractor Key Personnel.	11
1.10.6 Project Manager (PM) and Alternate.	12
1.10.7 Quality Control Manager (QCM).	12
1.10.8 Quality Control Inspectors (QCI).	12
1.10.9 Phase In /Phase Out Period.	12
1.11 Emergency Services.	13
1.11.1 Emergency Medical Treatment.	13
1.11.2 Accident Reporting.	13
1.12 Safety, Environment and OSHA.	14
1.12.1 Safety.	14
1.12.2 Safety Plan.	15
1.12.3 Spill Plan.	15
1.13 Environmental Compliance.	16
1.13.1 Safety Data Sheets (SDS).	16
1.14 Work Control.	17
1.14.1 Allowable Work Hours.	17
1.14.2 Work Schedule.	17
1.14.3 Schedule Work.	17
1.14.4 Status Reports.	17
1.14.5 Coordination With customers:	18
2.0 Definitions and Acronyms.	19
2.1 Definitions.	19
2.2 ACRONYMS.	23
3.0 Government Furnished Property, Equipment and Services.	26
3.1 Property.	26
3.2 Equipment.	26
3.3 Services.	26
3.4 Utilities.	26
3.5 Materials.	26
4.0 Contractor Furnished Items and Services.	27
4.1 General:	27
4.2 Contractor Vehicles.	27
4.3 Identification of Contractor Vehicles and Trailers.	27
4.4 Contractor Facilities.	27

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

4.5 Contractor Equipment and Tools.....	28
4.6 Permits.....	28
5.0 Specific Tasks for Grounds Maintenance.....	29
5.1 General.....	29
5.2 Description of Services.....	29
5.2.1 Scope.....	29
5.2.2 Service High Visibility Areas – TE 8.2 to TE 8.4 (Improved Grounds – Areas A, B and C)	30
5.2.2.1 DoDD School On Red Cloud.....	30
5.2.3 Mowing.....	30
5.2.4 Edging.....	31
5.2.5 Trimming.....	32
5.2.6 Fertilizing and Liming.....	33
5.2.7 Weed Control.....	33
5.2.8 Remove Debris, Leaves, and Litter.....	33
5.2.9 Tree Pruning – Crepe Myrtle.....	34
5.2.10 Hedge and Shrub Maintenance.....	34
5.2.11 New Ammo Storage Point (ASP) Area.....	35
5.2.12 Special Services.....	35
5.2.12.1 Special Event Services.....	35
5.3 Service Common Areas – TE 8.5 (Semi-Improved Grounds)	36
5.3.1 Trimming, See paragraph 5.2.5 Trimming, above.....	36
5.3.2 Remove Debris, Leaves and Litter, See paragraph 5.2.8 Remove debris, Leaves and litter, above.....	36
5.3.3 Herbicide Application to Railroad Rights-Of-Way.....	36
5.4 Service Unimproved Areas – TE 8.6 (Unimproved Grounds)	39
5.4.1 Mowing Unimproved Areas:.....	39
5.4.2 Perimeter Fence Line / Cable Barrier, Old Landfill's and Lake Tholocco Dam Maintenance.....	40
5.4.3 Remove Debris, Leaves and Litter, See paragraph 5.2.8 Remove debris, Leaves and litter, above.....	41
5.5 Other Special Services.....	41
5.5.1 Special Equipment Requirements.....	41
6.0 Applicable Publications (Current Editions).....	42
6.1 Regulations, Publications, Manuals, Local Policies and Procedures.....	42

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

7.0	Mandatory Records and Report Forms.....	45
8.0	Attachment/Technical Exhibits (TEs).....	46
8.1	Technical Exhibit (TE-1) – Performance Requirements Summary.....	46
8.2	Technical Exhibit (TE-2) – Historical Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services - Area A.	46
8.3	Technical Exhibit (TE-3) – Historical Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services - Area B.	46
8.4	Technical Exhibit (TE-4) – Historical Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services - Area C.	46
8.5	Technical Exhibit (TE-5) – Historical Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services – Semi-Improved.	46
8.6	Technical Exhibit (TE-6) – Historical Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services - Unimproved.....	46
8.7	Technical Exhibit (TE-7) – Historical Temperature and rainfall data.	46
8.8	Technical Exhibit (TE-8) – Deliverables Schedule.	46
8.9	Technical Exhibit (TE-9) – Approved Herbicides.	47
8.10	Technical Exhibit (TE-10) – Work Capability Levels.	47
8.11	Technical Exhibit (TE-11) - General Locations of Internal Fencing and Cable Barriers, Cantonment Grounds Maintenance Contract.	47
8.12	Technical Exhibit (TE-12) - Example Payment Calculations When RESD is Used.	47

1.0 General.

This is a non-personal services contract to provide Grounds maintenance Services for the U.S. Army Garrison Ft. Rucker, AL.

- The Government will not exercise any supervision or control over the contract service providers.
- The Contractor shall perform to the standards specified in this Performance Work Statement (PWS).
- Contract service providers shall be accountable solely to the Contractor who, in turn is responsible to the Government.
- The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to complete the requirements as outlined and defined in this PWS.

1.1 Description of Services/Introduction.

The Contractor shall provide all personnel, equipment, supplies, facilities, transportation, tools, materials, supervision, and other items and non-personal services necessary to perform all grounds maintenance service tasks and frequencies as described and defined in this Performance Work Statement (PWS), Part 5 Specific Tasks and Part 8 Attachment/Technical Exhibits.

- The Contractor shall perform to the standards in this contract.

1.2 Background.

The Mission of the U.S. Army Aviation Center of Excellence (AVCOE) and Fort Rucker, a Training and Doctrine Command (TRADOC) Installation, is to train military, civilian, and international personnel in aviation and leadership skills; to develop the doctrine, training, leader development, organization, material, and soldiers for Army Aviation's future war fighting requirements; manage available resources effectively and efficiently; and provide facilities and services in a safe environment with a superior quality of life.

Fort Rucker is located on gently rolling terrain with elevations averaging between 200 and 300 feet above mean sea level. Average monthly temperature ranges from 52 F° to 79 F°, with an overall average temperature of 67 F°. The extreme temperatures range from an average low of 40 F° in the winter to an average high of 91 F° in the summer. The average annual precipitation is 52.6 inches. Attachment 3, "Historical Temperature and Rain Fall Data – Cairns AAF" is a listing of the historical temperature and rainfall data from 2000 to 12 DEC 2024.

Hurricane season for Fort Rucker and the rest of the Gulf Coast lasts from June through November each year, with the peak being mid-September. Between the years 1900 to 2022, approximately eleven (11) hurricanes have made a direct hit

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

in Alabama. Out of these eleven (11) hurricanes, three (3) were Category 3 or higher.

Fort Rucker consists of approximately 91 square miles within Dale and Coffee counties in southeast Alabama. The nearest civilian community is Daleville, which is adjacent to the cantonment area on the southern boundary of the Installation. Fort Rucker is accessible by ground (via Highway 123, Highway 27, Highway 84, Highway 85, Highway 134, Highway 231, Highway 248, Highway 249, Andrews Avenue and Rucker Blvd), and by air (via Dothan Airport). Freight access is also available via railway.

Fort Rucker consists of 63,038 acres (57,772 acres within the Fort Rucker boundaries, 3,600 acres owned outside the Installation, and 1,666 acres leased outside the Installation). There are approximately 863 buildings and 120 training and testing facilities located on Fort Rucker.

Fort Rucker supports a daytime population of about 13,885, including about 5,800 people in uniform, 7,600 civilian and contract employees, and about 3,300 military Family member residents. Approximately 6,500 students attend training, education, and professional development courses at the Installation each year. The installation supports more than 67,000 active-duty dependents and retired military personnel and dependents.

1.3 Objectives.

The Contractor shall ensure all work accomplished as fulfillment of this PWS meets all applicable Federal, State, and local laws, regulations, directives, and other requirements (LOR) (See Definitions & Acronyms, 2.2 Acronyms --- Legal and Other Requirements) to include, but not limited to the documents in Part 6 Applicable Publications.

1.4 Scope.

The Contractor shall inspect, service and maintain grounds of Fort Rucker, Al. The work shall include scheduling and performance of mowing and trimming; leaf and debris removal; hedge, and shrub pruning, and fertilization; policing of areas; and other associated work as directed by the Contracting Officer's Representative (COR) or Alternate Contracting Officer's Representative (ACOR). The Contractor shall provide all work necessary to maintain the grounds to the standards specified herein.

- The Contractor shall provide for shrub and tree preservation and protection during all grounds maintenance activities as specified by this PWS.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

1.5 Period of Performance (PoP).

The period of performance shall be for one (1) Base Year of 12 months and FOUR (4) 12-month option years. The Period of Performance reads as follows:

Phase-in Period	DATE TBD
Base Year	DATE TBD
Option Year I	DATE TBD
Option Year II	DATE TBD
Option Year III	DATE TBD
Option Year IV	DATE TBD
Option Year V	DATE TBD
Option Year VI	DATE TBD

1.6 Traffic Flow.

The Contractor shall maintain the free flow of vehicular and pedestrian traffic while conducting grounds maintenance service tasks.

1.7 Restoration of Real Property Damage.

Any damage to Government Real Property by the Contractor's operations shall be restored to the original state at no additional cost to the Government (e.g., structural damage, damage to landscape or fencing, et al).

1.8 General Information.

1.8.1 Place of Performance

The work to be performed under this contract will be performed at Fort Rucker, Al., at the locations listed in **TE 8.2 to TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

1.8.2 Recognized Holidays.

New Year's Day	Labor Day
Martin Luther King Jr.'s Birthday	Columbus Day
President's Day	Veteran's Day
Memorial Day	Thanksgiving Day
Independence Day	Christmas Day
Juneteenth	

1.8.3 Hours of Operation.

Normal hours of operation are between the hours of **0700 – 1600**, Monday through Friday, excluding Federal holidays or when the Government facilities are closed due to local or national emergencies, administrative closings, or similar Government directed facility closings.

- Work performed outside of these times and/or days must be pre-approved by the KO or COR.
- The Contractor shall coordinate with COR to establish a schedule to conduct business if services are required outside of normal hours of operation.
- The Contractor shall maintain an adequate workforce for the uninterrupted performance of all tasks defined within this PWS when Government facilities are not closed for the above reasons.

1.8.4 Installation Closures.

When an unforeseen installation closure occurs on a regularly scheduled day of work, the Contractor shall reschedule the work to be performed the following day unless the following day is a Saturday, Sunday, a recognized Federal holiday, and when routine work is not scheduled for that day; or reschedule the work for the next business day following the closure.

1.8.4.1 Days of No Scheduled Activities (DONSA).

The installation has historically granted military personnel (Enlisted and Officers) DONSA, for example, the Friday after Thanksgiving, in addition to the listed Federal holidays above.

- DONSA are not considered a day of excused absence for the Government civilian work force or Contractor employees.
- If a DONSA affects scheduled contract work or access to facilities, the work in affected facilities may be rescheduled to compensate for the DONSA.
- However, announced DONSA or exodus of military personnel may provide the Contractor with an opportunity for unrestricted access to facilities and areas or uninterrupted performance of work (i.e. training facility and area maintenance and supply inventories).
- The Contractor shall vary work schedules to take full advantage of such opportunities by planning maintenance that is better accomplished when personnel are not using facilities during those times.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

1.8.5 Emergency Delays.

- If the Contractor determines unsafe weather conditions or work environment is cause for an interruption of services, the Contractor shall notify the COR (2) hours prior to curtailing operations **(See Deliverables Schedule, TE 8.8 Deliverables 01).**
 - The Contractor shall obtain COR approval to resume operations.
- The Contractor shall coordinate with the DPW designated representative(s) in preparation for and during emergency operations situations such as inclement weather, flood, active shooter, fire, or other emergency situations.

1.8.5.1 National Defense Emergency.

In the event of a National Defense Emergency affecting Fort Rucker, the Fort Rucker POC will immediately notify the contract POC. At that time, the contractor shall take immediate steps to cease all activities on the installation(s) and will cause all personnel to leave the installation(s) property until notice is given by the installation and Fort Rucker POC that National Defense Emergency conditions are no longer in effect.

1.8.6 Unforeseen Closures of Service Areas.

When an unforeseen closure occurs on a regularly scheduled day of work (i.e., severe weather, training holiday, day of mourning, etc.).

- The Contractor shall reschedule the service on any day satisfactory to the customer and minimizes impact on the Contractor's normal work schedule.

1.8.7 Type of Contract.

The government will award a FIRM FIXED PRICE (FFP) contract with some "As Required" CLIN's.

1.8.8 Security Requirements and Training.

1.8.8.1 Access and General Protection/Security Policy and Procedures.

Contractor and all associated sub-contractor's employees shall provide all information required for background checks to meet installation access requirements to be accomplished by installation Provost Marshal Office, Director of Emergency Services or Security Office.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- Contractor workforce must comply with all personal identity verification requirements (FAR clause 52.204-9, Personal Identity Verification of Contractor Personnel) as directed by DOD, HQDA and/or local policy.
- In addition to the changes otherwise authorized by the changes clause of this contract, should the Force Protection Condition (FPCON) at any individual facility or installation change, the Government may require changes in contractor security matters or processes.
- In the event of a National Defense Emergency affecting Fort Rucker, the COR will immediately notify the contract POC. At that time, the contractor shall take immediate steps to cease all activities on the installation(s) and will cause all personnel to leave the installation(s) property until notice is given by the installation and the COR POC that the National Defense Emergency conditions are no longer in effect.

1.8.8.2 Physical Security.

At the close of each work period, the contractor shall ensure government facilities, equipment, and materials are secured.

1.8.8.3 Security Training.

1.8.8.3.1 Anti-Terrorism (AT) Level I Training.

IAW Department of Defense Instruction (DoDI) 2000.16, Vol. 1 DoD Antiterrorism Standards and Army Regulation (AR) 525-13 Antiterrorism, all Contractor employees, including subcontractor employees, requiring access to Army installations, facilities, or controlled access areas shall complete Antiterrorism (AT) Level I awareness training within 30 calendar days after contract start date.

- The Contractor shall submit certificates of completion for each affected contract employee and subcontractor employee to the KO or COR within 30 calendar days after completion of training by all employees and subcontractor personnel on a recurring annual basis.
- AT Level I awareness training is available at the following site: <http://jko.jten.mil> (**See Deliverables Schedule, TE 8.8 Deliverables 02**).
- If access to a computer is not available, the Government will provide AT Level I training to Contractor employees within 30 business days after contract start and maintain a copy of the attendance roster for one (1) year.
- Any Contractor hired after contract start will be required to receive AT Level I training within 30 calendar days either online or as provided by the Government.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- The Contractor must present the training certificate to the KO or designated Government representative/COR within 30 calendar days.
(See Deliverables Schedule, TE 8.8 Deliverables 03).

1.8.8.3.2 iWATCH Training.

The Contractor shall brief the local iWATCH program (training standards provided by the Installation Anti-Terrorism Officer (ATO)) to all its' employees and associated subcontractors.

- This training is used to inform employees of the types of behavior to watch for and instruct employees to report suspicious activity to the Fort Rucker Military Police and the COR.
- The Contractor shall complete the training within 30 calendar days after contract award and within 30 calendar days of new employees commencing performance and send to the KO or designated Government representative/COR via both electronic and paper copy within 30 calendar days of completion (See Deliverables Schedule, TE 8.8 Deliverables 04).

1.8.9 Local Health Protection Conditions

Contractor will comply with all national and DoD policies with regard to health protection issues including pandemic outbreaks.

- The Contractor shall comply with installation and higher headquarters policies aimed at mitigating the spread of dangerous communicable diseases.

1.8.10 Key Control.

The Contractor shall establish and implement methods of making sure all keys/key cards issued to the Contractor by the Government are not lost or misplaced and are not used by unauthorized persons. NOTE: All references to keys include key cards.

- No keys issued to the Contractor by the Government shall be duplicated.
- The Contractor shall develop procedures covering key control that shall be included in the QCP.
- Such procedures shall include turn-in of any issued keys by personnel who no longer require access to locked areas.

1.8.11 Lost Keys.

- No keys issued to the Contractor by the Government shall be duplicated.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- The Contractor shall immediately report any occurrences of lost keys/key cards to the KO in the event keys, other than master keys are lost or duplicated.
- In the event a key is lost, the Contractor shall, upon direction of the KO, have the Government re-key or replace the affected lock or locks.
- When the replacement of locks or re-keying is performed by the Government, the total cost of re-keying or the replacement of the lock or locks shall be deducted from the monthly payment due the Contractor.
- In the event a master key is lost, all locks and keys for that system shall be replaced by the Government and the total cost deducted from the monthly payment due the Contractor.

1.8.12 Prohibited use of Government provided keys or key cards.

The Contractor shall prohibit the use of Government issued keys/key cards by any persons other than the Contractor's employees.

- No keys issued to the Contractor by the Government shall be duplicated.
- The Contractor shall prohibit the opening of locked areas by Contractor employees to permit entrance of persons other than Contractor employees engaged in the performance of assigned work in those areas, or personnel authorized entrance by the KO.

1.8.13 Post Award Conference/Periodic Progress Meetings.

The Contractor shall attend the post award conference convened by the Contracting Activity or Contract Administration Office as agreed upon and stated in the contract award document.

- When the KO, COR and DPW management meets with the Contractor to review the Contractor's performance, written minutes of meetings will be recorded by the Government and signed by the Requirements Authority (RA) and the KO.
- The written minutes will be distributed within five (5) business after the meeting.
- If any party does not concur with any portion of the minutes, the non-concurrence shall be provided in writing to the KO/COR within two (2) workdays following receipt of the minutes.
- Notwithstanding the Contractor's responsibility for total management during the performance of this contract, the administration of the contract requires maximum coordination and cooperation between the Government and the Contractor.

1.9 Government Roles and Responsibilities.

1.9.1 Contracting Officer (KO).

The KO is the only person authorized to make any changes in any of the requirements listed on this PWS; notwithstanding any provisions contained elsewhere in this contract, said authority remains solely with the KO.

- In the event the Contractor makes any change at the direction of any person other than the KO, the change will be considered to have been made without authority and solely at the risk and expense of the Contractor.
- All contract administration will be effected by the KO.
- Communications pertaining to contractual administrative matters shall be addressed to the KO.
- No changes in or deviations from the terms and conditions shall be effected without a written modification to the contract, executed by the KO authorizing such changes.
- The KO will approve all Deliverables and plans required in this PWS.

1.9.2 Contracting Officer's Representative (COR).

The KO will appoint a COR during the performance of this requirement.

- Additional Government personnel may be designated to assist in contract oversight IAW AR 70-13 Management and Oversight of Service Acquisitions.
- Other surveillance personnel may be designated as COR and shall be trained and appointed IAW DoDI 5000.72, Department of Defense (DoD) Standard for Contracting Officer's Representative (COR) Certification.
- The COR will provide assistance in identification and resolution of problems, conflicts in priority, subtask requirement definitions, and other operations type problems.
- The COR will perform IAW the responsibilities and duties identified in the appointment letter.

1.9.3 COR Authority.

A letter of designation will be issued to the COR by the KO.

- A copy of the letter will be sent to the Contractor.
- The letter of designation states the responsibilities and limitations of the COR, especially with regard to changes in cost, price estimates, or changes in delivery dates.
- The COR is not authorized to change any of the terms and conditions with regard to cost, quantity, or schedule of the resulting order.

1.9.4 COR or Designated Government Representative Functions.

The COR or designated Government representative shall monitor all technical aspects of the contract and assists in contract administration.

- The COR or designated Government representative is authorized to perform the following functions:
 - assure the Contractor performs the technical requirements of the contract.
 - perform inspections necessary in connection with contract performance.
 - maintain written and oral communications with the Contractor concerning technical aspects of the contract.
 - issue written interpretations of technical requirements.
 - monitor, document, and report Contractor's performance and notify both the KO and Contractor of any deficiencies.
 - coordinate availability of Government-Furnished Property and provides direction or assistance for site entry requests of Contractor personnel.
 - Provide the contractor information regarding the DoD 3Rs (Recognize, Retreat, Report) Explosives Safety Education Program. More information at: <https://www.denix.osd.mil/uxo/>.

1.10 Specific Contractor Requirements, Roles and Responsibilities.

1.10.1 U.S. Residency.

All Contractor employees shall be legal U.S. residents.

- The Contractor shall immediately remove any employee that is not a legal U.S. resident.
- The Contractor personnel shall be able to communicate clearly in the English language.

1.10.2 Contractor Hiring Restrictions.

The Contractor shall not hire or subcontract with off-duty or former Government employees whose employment would result in a conflict of interest as defined in DOD 5500.7-R Joint Ethics Regulation 30 August 1993, to include change dated 17 November 2011.

1.10.3 Contractor Identification.

The Contractor shall ensure that personnel be identified as a Contractor to distinguish themselves (e.g., badge, company logo, or uniform) from Government employees.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- The Contractor shall ensure all correspondence and reports produced are marked as Contractor products or that Contractor participation is disclosed.
- Contractor owned/leased vehicles and trailers shall be clearly identified.

1.10.4 Standards of Conduct.

Contractor personnel's conduct shall not reflect discredit upon the Government. The Contractor shall ensure all personnel present a professional appearance while working on the Government installation.

- The Contractor's employees shall observe and comply with all local policies and procedures concerning fire, safety, environmental protection, sanitation, security, and possession of firearms or other lethal or illegal weapons or substance.
- The Contractor shall ensure all Contractor employees, providing services under this contract, conduct themselves and perform services in a professional, safe, and responsible manner.
- The Contractor shall remove, from the job site, any employee for reasons of misconduct or security.
- The Contractor shall ensure employee conduct complies with 41 USC §423, *Procurement Integrity*.
- The Contractor shall also ensure that no Contractor employees conduct political related activities or events on the installation.
- The removal of such a person shall not relieve the Contractor of the requirement to provide personnel to perform adequate and timely service.

1.10.5 Contractor Key Personnel.

Contractor shall provide a resume of key personnel, who will be designated in writing, to the KO within one week of the contract award (**See Deliverables Schedule, TE 8.8 Deliverables 05**).

These key personnel shall be available during normal duty hours. These individuals designated as key personnel shall be able to understand, speak, read, and write the English language.

The following contractor personnel are considered key personnel by the Government:

1. Project Manager (PM)
2. Quality Control Manager (QCM)
3. Quality Control Inspector (QCI)

1.10.6 Project Manager (PM) and Alternate.

The Contractor shall provide a PM who is responsible for the performance of the work.

- **The PM shall have five (5) years of experience in grounds maintenance management or a contract similar in scope and breadth to this solicitation.**
- The PM shall have full authority to act for the Contractor on all contract matters relating to daily operation of the contract.
- The name and contact information of the PM shall be provided to the KO and shall be present and on-site, and available during normal duty hours.
- In the circumstances when the PM is not available, the Contractor shall designate in writing an alternate who can perform the same duties during the absence.

1.10.7 Quality Control Manager (QCM).

The Contractor shall designate a full time QCM on site during normal duty hours.

- As a minimum, **the QCM shall have at least two (2) years of documented relative grounds maintenance services experience and shall be responsible for the overall management and implementation of the Contractor's Quality Control Plan.**

1.10.8 Quality Control Inspectors (QCI).

The Contractor shall designate QCI personnel sufficient to monitor Contract work to assure compliance with Government requirements.

- **QCIs shall have two (2) years of documented experience in quality control of grounds maintenance.**
- Depending on the size of the contract, the QCM may also serve as the QCI.

1.10.9 Phase In /Phase Out Period.

The Contractor shall prepare and submit (within ten (10) business days after contract award), a Phase In/Phase Out Plan to be implemented by the Contractor **(See Deliverables Schedule, TE 8.8 Deliverables 06).**

- The Contractor shall provide sufficient experienced personnel during the phase-in and phase-out period to ensure that the services are maintained at the required level of proficiency.
- During the phase-in, the Contractor shall observe all operations pertinent to the requirements of the PWS.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- The Contractor shall commence all operations required by this PWS by the end of phase in period.
- On the initial day of performance, the Contractor shall provide a work force which is fully qualified and capable of performing all work required under this contract.
- During the ten (10) business day transition period immediately prior to the end of the previous contract, the Contractor shall permit the successor Contractor (and the successor Contractor's employees) to observe and become familiar with any and all operations under the contract.
- The Contractor shall fully cooperate with the successor Contractor during Phase Out and the Government so as not to interfere with future work or duties.

1.11 Emergency Services.

1.11.1 Emergency Medical Treatment.

The Contractor or their employees shall immediately notify their supervisor of any incident requiring immediate emergency medical treatment.

- The Government may provide 911 emergency support ambulance service if available.
- If injuries incurred while an employee is performing work under this contract, the contractor shall verbally notify the KO/COR no later than **(NLT) two (2) hours** after an emergency medical event, followed by a documented summary of events **(See Deliverables Schedule, TE 8.8 Deliverables 07).**
- The Contractor shall be responsible for the emergency medical treatment services for Contractor personnel.
- **There are no emergency medical treatment facilities located on Fort Rucker.**

1.11.2 Accident Reporting.

The Contractor shall comply with 29 CFR 1904, Operational Safety and Health Administration (OSHA) Recordkeeping for reporting of all accidents resulting in death, injury, occupational disease, or adverse environmental impact.

- The Contractor shall provide a verbal report to the KO/COR within two (2) hours of each such occurrence **(See Deliverables Schedule, TE 8.8 Deliverables 08).**
- The contractor shall deliver a completed ENG Form 3394, United States Army Corps of Engineers Accident Investigation Report (or equivalent form), to the KO or designated Government representative/COR detailing the mishap within five (5) business days of occurrence, whenever the

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

incident involves personal injury or damage to government property **(See Deliverables Schedule, TE 8.8 Deliverable 09)**.

1.12 Safety, Environment and OSHA.

IAW para. 1.4 Scope, any apparent conflict between compliance (with such local, State, and Federal environmental and occupational safety laws, rules, and regulations) and the requirements of the contract shall be immediately brought to the attention of the KO and authorized representative(s) (i.e., Environmental Officer, Safety Officer and COR) verbally.

- The Contractor shall notify the KO and authorized representative(s) via email outlining the details for each said conflict such that a final resolution is derived **(See Deliverables Schedule, TE 8.8 Deliverables 10)**.
- The Contractor shall be liable for all fines, penalties, and costs that result from violations of, or failure to comply with para. 1.4 Scope.

1.12.1 Safety.

The Contractor shall safeguard and maintain all Government and Contractor property, as well as provide for the safety and well-being of personnel employed under this contract.

- The Contractor shall comply with 29 CFR Parts 1910 and 1925 and DODI 6055.07, Mishap Notification, Investigation, Reporting, and Record Keeping.
- The contractor shall investigate and report mishaps that occur as a result of a Government contractor's operation in which there is reported damage to DoD property or injury or occupational illness to DoD personnel.
- All unsafe acts or conditions fostered by the Contractor or Contractor personnel may be grounds for the KO to halt any and all Contractor performance until such unsafe conditions are corrected.
- The Contractor shall take due caution not to endanger personnel during performance of this contract.
- All Contractor employees shall wear a reflective vest or suitable substitute while working during darkness hours.
- Contractor shall be responsible for any injury to any Contractor's representative, or others, as well as for any damage to any personal or public property that occurs during the performance of this contract that is caused by the Contractor's fault or negligence.
- Upon discovery of a serious hazard such as, but not limited to, fire, or fuel spill, the Contractor shall immediately notify the COR/KO and designated authorized representatives verbally followed up with an email notification within one (1) hour **(See Deliverables Schedule, TE 8.8 Deliverable 11)**.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- As prescribed in FAR 52.222-41, the Contractor or subcontractor shall not permit any part of the services called for by this contract to be performed in buildings or surroundings or under working conditions provided by or under the control or supervision of the Contractor or subcontractor which are unsanitary, hazardous, or dangerous to the health or safety of the service employees.
- At all times, the contractor shall comply with the standards issued by the Secretary of Labor at 29 CFR Parts 1910 and 1925.
- The Contractor shall establish all required workplace safety programs sufficient to meet requirements in the aforementioned standards.
- As prescribed in 246.371(a), DFARS 252.246-7003 Notification of Potential Safety Issues, the contractor shall notify the COR as soon as practicable, but not later than 72 hours after discovering or acquiring credible information concerning potential safety issues. **(See Deliverables Schedule, TE 8.8 Deliverable 12)**

1.12.2 Safety Plan.

- The Contractor shall develop and implement a safety plan, to include an Accident Prevention Plan (APP), Activity Hazard Analysis (AHA), and fire and emergency action plan, for its employees.
- Plans will include an analysis of all significant hazards to life, limb, and property inherent in work performance and a plan for controlling hazards.
- The Contractor shall submit the safety plan to the KO/COR for review and acceptance within thirty (30) business days after contract award **(See Deliverables Schedule, TE 8.8 Deliverable 13)**.
- Revisions shall be submitted to the KO/COR five (5) business days prior to the effective date of change **(See Deliverables Schedule, TE 8.8 Deliverable 14)**.
- The contractor shall ensure employees hired to perform grounds maintenance are provided information regarding the DoD 3Rs (Recognize, Retreat, Report) Explosives Safety Education Program. More information at: <https://www.denix.osd.mil/uxo/>.

1.12.3 Spill Plan.

The Contractor shall comply with the Fort Rucker's Spill Prevention Control and Countermeasure Plan and environmental work instructions located at <https://fortRucker-env.com>.

- The contractor shall submit a Site-Specific Spill Plan (AVCOE Form 2719) to the KO for approval within thirty (30) days of contract award IAW Fort

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

Rucker's Installation Spill Contingency Plan **(See Deliverables Schedule, TE 8.8 Deliverable 15).**

- The Contractor shall notify the COR/ACOR **IMMEDIATELY** if the Contractor spills or releases any hazardous substances, *i.e.*, substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification* **(See Deliverables Schedule, TE 8.8 Deliverable 16).**
- If any hazardous material gets on the ground, in a drain or in a waterway it must **IMMEDIATELY** be reported by dialing 911 and by calling, Fort Rucker DPW-ENRD, 334-255-1657 **(See Deliverables Schedule, TE 8.8 Deliverable 17).**
- The contractor performing this work must have on hand (at the project site) SDS's for any chemicals used as part of this project.

1.13 Environmental Compliance.

The contractor shall implement the following environmental objectives in accordance with FAR 23.4; FAR 23.7; FAR 52.223-1 through 52.223-5; and based on EPA-issued guidance) to include:

- Maximize the utilization of environmentally preferable products;
- Maximize the utilization of bio-based products. See USDA-designated items at <http://www.biopreferred.gov> or 7 CFR part 3201;
- Maximize the reutilization of nonhazardous and recovered materials;
- Promote recycling and other cost-effective waste reduction;
- Eliminate or reduce the generation of hazardous waste and the need for special material processing (including special handling, storage, treatment, and disposal);
- Promote energy-efficiency and water conservation.

1.13.1 Safety Data Sheets (SDS).

For materials that have Safety Data Sheets (SDS) associated with them, the Contractor shall submit the SDS to the KO or designated Government representative/COR for approval five (5) business days after contract award **(See Deliverables Schedule, TE 8.8 Deliverable 18).**

- The Contractor shall adhere to all applicable requirements of the Installation Hazardous Waste Management Plan (HWMP) and work instructions;
- The Contractor shall provide all materials, labor, training, transportation, and equipment for the handling and storage of hazardous materials or toxic materials.
- The SDS includes information such as the properties of each chemical; the physical, health, and environmental health hazards; protective

Ft. Rucker, AL. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

measures; and safety precautions for handling, storing, and transporting the chemical. This information shall be communicated to personnel IAW 29 CFR 1910.1200.

1.14 Work Control.

The Contractor shall plan and schedule work to assure material, labor, and equipment are available to complete work requirements with regard to the established time limits and quality standards.

1.14.1 Allowable Work Hours.

All work shall be performed during regular working hours specified in paragraph 1.8.3 unless prior approval is granted by the COR/KO.

1.14.2 Work Schedule.

The Contractor shall arrange work to prevent interference with the normal occurrence of Government business. In those cases where some interference is unavoidable, the Contractor shall make every effort to minimize the impact of the interference and its effects.

1.14.3 Schedule Work.

Proposed work schedules shall be submitted for approval to the KO and COR monthly, at least five (5) working days prior to the start of the schedule month, and shall indicate the proposed date of accomplishment of all required services by location (**See Deliverables Schedule, TE 8.8 Deliverable 19**).

- The KO and COR shall be notified at least two (2) working days in advance of any changes to the scheduled date of any work requirements. (**See Deliverables Schedule, TE 8.8 Deliverable 20**)

1.14.4 Status Reports.

The Contractor shall prepare and provide, prior to 0900 on a daily basis, status reports for all mowing services required by the contract. (**See Deliverables Schedule, TE 8.8 Deliverable 21**) The status reports shall be current (as of close of business the previous workday) and shall contain, at a minimum;

- the date the report was prepared;
- which areas (or portions of areas) were completed on the previous workday (by number and/or designation, as applicable);
- which areas (or portions of areas) have been completed in this cycle to date (by number and/or designation, as applicable);

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- whether the Contractor is ahead or behind schedule and the amount thereof;
- and a statement by the Quality Control Manager verifying the accuracy of the report.

1.14.5 Coordination With customers:

Contractor shall coordinate with appropriate “points of contact (POC)” at least one (1) day prior to schedule cutting to ensure that locked areas are accessible for cutting per approved schedules.

- DPW will provide a listing of POC’s, along with phone numbers, to the Contractor at post award meeting.

PART 2 DEFINITIONS & ACRONYMS

2.0 Definitions and Acronyms.

2.1 Definitions.

Acceptable Quality Level (AQL).

The AQL is the maximum percent defective (or the number of defects per hundred units) that, for purposes of sampling inspection can be considered satisfactory.

Child, Youth and School Services (CYS).

Overarching naming convention for Child Development Center (CDC); Youth Activity Center; and School Age Services (SAS) is Child, Youth and School, Services (CYS); shall be used when referencing all programs.

Contractor.

A supplier or vendor awarded a contract to provide specific supplies or service to the Government. The term used in this contract refers to the prime.

Contractor Acquired Property (CAP).

Property acquired, fabricated, or otherwise provided by the Contractor for performing a contract and to which the Government has title.

Contracting Officer (KO).

A person with authority to enter into, administer, and or terminate contracts, and make related determinations and findings on behalf of the Government. Note: The only individual who can legally bind the Government.

Contracting Officer's Representative (COR).

An employee of the U.S. Government appointed by the contracting officer to administer the contract. Such appointment shall be in writing and shall state the scope of authority and limitations. This individual has authority to provide technical direction to the Contractor as long as that direction is within the scope of the contract, does not constitute a change, and has no funding implications. This individual does NOT have authority to change the terms and conditions of the contract.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

Deficient Service.

A service output that does not meet the standard of performance associated with the Performance Work Statement.

Deliverable.

Objective evidence that can be physically delivered but may include non-manufactured things such as meeting minutes or reports.

Equipment.

A tangible item that is functionally complete for its intended purpose, durable, nonexpendable, and needed for the performance of a contract. Equipment is not intended for sale and does not ordinarily lose its identity or become a component part of another article when put into use. Equipment does not include material, real property, special test equipment or special tooling.

Government Furnished Property (GFP).

Property in the possession of, or directly acquired by, the Government and subsequently furnished to the Contractor for performance of a contract. Government-furnished property includes, but is not limited to, spares and property furnished for repair, maintenance, overhaul, or modification. Government-furnished property also includes Contractor-acquired property if the Contractor-acquired property is a deliverable under a cost contract when accepted by the Government for continued use under the contract.

Government Property.

All property owned or leased by the Government. Government property includes both Government- furnished property and Contractor-acquired property. Government property includes material, equipment, special tooling, special test equipment, and real property. Government property does not include intellectual property and software.

Government Project Manager.

The DPW Project Engineer/Technician/COR assigned to manage this PWS.

Legal and Other Requirements.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

Applicable Federal, State, local, DoD and Army laws, codes, regulations and other requirements.

Loss of Government Property.

Unintended, unforeseen or accidental loss, damage, or destruction of Government property that reduces the Government's expected economic benefits of the property. Loss of Government property does not include occurrences such as purposeful destructive testing, obsolescence, normal wear and tear, or manufacturing defects. Loss of Government property includes, but is not limited to: Items that cannot be found after a reasonable search. Theft Damage resulting in unexpected harm to property requiring repair to restore the item to usable condition; or Destruction resulting from incidents that render the item useless for its intended purpose or beyond economical repair. Contractor shall prepare damage reports monthly and submit to COR.

Material.

Property that may be consumed or expended during the performance of a contract, component parts of a higher assembly, or items that lose their individual identity through incorporation into an end-item. Material does not include equipment, special tooling, and special test equipment or real property.

Non-Personal Services.

The personnel rendering the services are not subject; either by the contract's terms or by the manner of its administration, to the supervision and control usually prevailing in relationships between the Government and its employees. Non personal service contracts are authorized by the Government in accordance with FAR 37.012, under general contracting authority, and do not require specific statutory authorization.

Performance Requirements Summary (PRS).

Identifies the key service outputs of the Contractor.

Physical Security.

Actions that prevent the loss or damage of Government property.

Property.

All tangible property, both real and personal.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

Property Records.

Records created and maintained by the Contractor in support of its stewardship responsibilities for the management of Government property.

Provide.

To furnish, as in Government-furnished property, or to acquire, as in Contractor-acquired property.

Quality Assurance.

The Government procedures to verify that services being performed by the Contractor are performed according to acceptable standards.

Quality Assurance Surveillance Plan (QASP).

An organized document written by the Government specifying the surveillance methodology used for surveillance of Contractor performance.

Quality Control.

All necessary measures taken by the Contractor to assure that the quality of an end product or service shall meet contract requirements.

Real Property.

See Federal Management Regulation 102-71.20 (41 CFR 102-71.20).

Sensitive Property.

Property potentially dangerous to the public safety or security if stolen, lost, or misplaced, or that shall be subject to exceptional physical security, protection, control, and accountability. Examples include weapons, ammunition, explosives, controlled substances, radioactive materials, hazardous materials or wastes, or precious metals.

Spill Plan.

A plan designed to identify steps to prevent a discharge of one or more hazardous substances that adversely impact, or threaten to adversely impact, human health, welfare or the environment and requires an immediate response.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

Subcontractor.

One that enters into a contract with a prime Contractor. The Government does not have privity of contract with the subcontractor.

Wide Area Work Flow (WAWF).

A secure web system for electronic invoicing, receipt, and acceptance. WAWF allows Government vendors to submit and track invoices and receipt/acceptance documents over the web and allows Government personnel to process those invoices in a real-time, paperless environment.

Work Day.

The number of hours per day the Contractor provides services in accordance with the contract.

Work Week.

Monday through Friday, unless specified otherwise (Installation specific or as defined by the Collective Bargaining Agreement).

2.2 ACRONYMS.

ACC	Army Contracting Command
ACS	Army Community Service
ACOR	Alternate Contracting Officer's Representative
ANSI	American National Standards Institute
AQL	Acceptable Quality Level
AR	Army Regulation
ATO	Anti-Terrorism Officer
CAP	Contractor Acquired Property
CDC	Child Development Center
CFE	Contractor Furnished Equipment
CFM	Contractor Furnished Material
CFP	Contractor Furnished Property
CFR	Code of Federal Regulations
CLIN	Contract Line Item Number
CLS	Common Levels of Support
COR	Contracting Officer's Representative
CPARS	Contractor Performance Assessment Reporting System
DA	Department of the Army

Ft. Rucker, AL. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

DES	Directorate of Emergency Services
DFARS	Defense Federal Acquisition Regulation Supplement
DoD	Department of Defense
DOL	Department of Labor
DPW	Directorate of Public Works
ENV	Environmental
FAR	Federal Acquisition Regulation
FIPS	Federal Information Processing Standards
FPCON	Force Protection Condition
GFE	Government-Furnished Equipment
GFM	Government-Furnished Material
GFP	Government-Furnished Property
GOV	Government
HQDA	Headquarters Department of the Army
HSPD	Homeland Security Presidential Directive
HWMP	Hazardous Waste Management Plan
IAW	In Accordance With
IMCOM	Installation Management Command
KO	Contracting Officer
LOR	Legal and Other Requirements
N/A	Not Applicable
NLT	Not Later Than
OCI	Organizational Conflict of Interest
OPSEC	Operational Security
OSHA	Occupational Safety and Health Administration
PAM	Pamphlet
PIEE	Procurement Integrated Enterprise Environment
PM	Project Manager
POC	Point of Contact
PoP	Period of Performance
PRS	Performance Requirements Summary
PUB	Publication
PWS	Performance Work Statement
QA	Quality Assurance
QAP	Quality Assurance Program
QASP	Quality Assurance Surveillance Plan
QC	Quality Control
QCP	Quality Control Plan
RCRA	Resource Conservation and Recovery Act
SAM	System for Award Management
SDS	Safety Data Sheets
SPM	Surveillance and Performance Monitoring
SSP	Service Support Program

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

TARP	Threat Awareness and Reporting Program
TE	Technical Exhibit
U.S.C.	United States Code
WAWF	Wide Area Workflow
WD	Wage Determination
YC	Youth Centers

PART 3
GOVERNMENT FURNISHED PROPERTY, EQUIPMENT, AND SERVICES

3.0 Government Furnished Property, Equipment and Services.

3.1 Property.

There is no Government-furnished material (GFM), property (GFP) or equipment (GFE) provided under this contract.

3.2 Equipment.

There is no Government-furnished equipment provided under this contract.

3.3 Services.

Police and fire protection shall be provided by the Government when working on Fort Rucker.

3.4 Utilities.

The Government will provide limited amounts of water.

3.5 Materials.

There are no Government-furnished materials provided under this contract.

PART 4

CONTRACTOR FURNISHED ITEMS AND SERVICES

4.0 Contractor Furnished Items and Services.

4.1 General:

The Contractor shall provide all facilities, vehicles, equipment, herbicides, parts, tools, fuel, oil, materials, and any other items required to perform all contract requirements.

- All Contractor furnished property and material shall meet applicable Federal, State, local, Department of Defense and Army laws, codes, and regulations.
- The Contractor's property shall be operational as intended by the manufacturer, safe, clean, and suitable for use at a military installation.
- All Contractor furnished property and equipment are subject to COR/KO inspection at all times.

4.2 Contractor Vehicles.

All Contractor-owned and/or operated vehicles and trailers operating on the installation shall be road worthy.

4.2.1 Evidence of vehicle ownership and vehicle liability insurance are required for each vehicle to be operated on the installation and must be presented upon demand by the appropriate authorities.

4.2.2 All vehicles and trailers used in the performance of this contract shall be in operable condition and meet local, State, and Federal safety requirements. Vehicles and trailers found to be unsafe and unable to function as designed, shall be removed from the installation.

4.3 Identification of Contractor Vehicles and Trailers.

The company name shall be displayed on each of the Contractor's vehicles and trailers in a manner and size that is clearly visible. All vehicles and trailers shall display a valid state license plate and safety inspection sticker, if applicable, and shall be maintained in good repair.

4.3.1 The Contractor shall remove all vehicles, trailers, and equipment from the installation at the end of each workday, unless authorized by the COR/KO to stage equipment for projected work requirements.

4.4 Contractor Facilities.

Ft. Rucker, AL. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

The Contractor shall secure the necessary office space and other facilities required for the performance of this contract off the military installation.

4.5 Contractor Equipment and Tools.

The Contractor shall furnish all tools and equipment required for the performance of this contract.

4.5.1 All mowers, regardless of type, shall have safety guards on discharge areas, over all belts and pulleys, and be equipped with safety kill switches.

4.5.2 All string trimmers shall have manufacturer's safety guards or Government approved safety guards properly installed on them at all times.

4.5.3 Tractors and self-propelled mowers over twenty (20) drawbar horsepower and/or exceeding 1,000 pounds gross weight shall have safety discharge guards on the front and rear of each mower and shall be equipped with an approved rollover protection system, flashers, turn signals and seatbelts.

4.5.4 The Contractor's tractors and other slow-moving equipment shall be equipped with the slow-moving vehicle placards.

4.5.5 The Contractor shall take such measures to protect the public and property from foreign materials thrown from rotary mowers and other rotating equipment while operating in public use areas and on public roadways.

4.5.6. All gas/diesel powered equipment shall be maintained in a manner to minimize the possibility of a release of petroleum or other hazardous materials while in operation.

- Equipment shall be inspected daily or prior to each use for the presence of leaking fluids.
- Leaking components shall be repaired prior to operation.
- Records of inspections shall be maintained by the Contractor and made available to the COR upon request.

4.6 Permits.

The Contractor shall obtain all appointments, licenses, and permits required for performance of work and for complying with all applicable Federal, State, and local laws. Permits and licenses shall be provided to the COR before work commences.

PART 5 SPECIFIC TASKS

5.0 Specific Tasks for Grounds Maintenance.

5.1 General.

The Contractor shall provide all management, tools, equipment, and labor necessary to ensure that grounds maintenance services performed at Fort Rucker are IAW the standards specified in this PWS.

The work shall include:

- scheduling and performance of mowing and trimming;
- leaf and debris removal;
- hedge, and shrub maintenance, and fertilization as ordered;
- policing of areas;
- and other associated work as directed by the Contracting Officer's Representative (COR) or Alternate Contracting Officer's Representative (ACOR).

5.2 Description of Services.

5.2.1 Scope.

The Contractor shall provide Grounds Maintenance for all **High Visibility** (Improved Grounds), **Common Areas** (Semi-Improved Grounds), and **Unimproved** Grounds.

- The Contractor shall ensure all work accomplished maintains and presents a healthy, clean, neat, and professional appearance to all grounds included, and covered by this contract, in support of mission requirements for users, residents, and visitors.
 - The Contractor shall Maintain grass height IAW TE 8.10, Work Capability Levels and TE 8.2 to TE 8.6, Service Frequencies.
 - All work shall be performed by personnel qualified in accordance with (IAW) applicable laws and regulations.
 - Contractor may be required to plant and / or replace contractor damaged trees and or shrubs.
 - Plants selected for planting should be nursery grown, vigorous and free of pests and diseases.
 - Trees and shrubs should conform to the American Standard for Nursery Stock (ANSI Z60.1-2014).

Ft. Rucker, AL. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- Trees and shrubs shall be selected based on correct USDA Plant Hardiness Zones for plants adaptable to the geographic region web link: <https://planthardiness.ars.usda.gov/PHZMWeb/>.
- The Contractor shall replace any replacement trees or shrubs planted that die within one (1) year, at no cost to the Government.
- The Contractor shall set the mower height to three (3) inches for all areas.
- All work shall be performed by personnel qualified in accordance with (IAW) applicable laws, regulations, and Technical Exhibit (TE 2).

5.2.2 Service High Visibility Areas – TE 8.2 to TE 8.4 (Improved Grounds – Areas A, B and C).

High Visibility Areas are developed areas of the installation that require an intensive level of maintenance. The work performed in these areas by the Contractor shall include:

- mowing grass,
- edging and trimming grass,
- removing grass trimmings from paved areas,
- applying fertilizer and/or lime as ordered,
- mowing athletic fields,
- removing leaves (see paragraph 5.2.8 for specifications).
- removing grass from cracks in sidewalks, other improved walkways and all non-parking pavements within TE boundaries.
- and litter/debris control.

5.2.2.1 DoDD School On Red Cloud

- School has 5 locations in the recess / play area that have commercial poured-in-placed rubber playground surfacing.
 - Contractor shall take **EXTREME** care when cutting grass and edging at these 5 locations.
 - Contractor shall **NOT** travel over, turn around on, or otherwise operate **ANY** grounds maintenance equipment on poured-in-place rubber playground surfacing.

5.2.3 Mowing.

High Visibility Areas, approximately **950** acres, are indicated in the Installation Grounds Maps referenced in **TE 8.2 to TE 8.4, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.** The Contractor

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

shall:

- remove trash, litter, tree limbs (less than 4 inches in diameter), debris, etc., prior to **each mowing**.
- Roadways shall be cut from the road edge to the tree line.
- Paved areas and walkways shall be free of lawn clippings/debris the same day the mowing is performed.
- The Contractor shall mulch mow the grass and remove visible grass clumps after mowing, before leaving the work area.
- Grass to be maintained **IAW TE 8.10, Work Capability Levels and TE 8.2 to TE 8.4, Service Frequencies**.
- **The contractor shall bag and remove ALL grass clippings, each cutting, from the**
 - **“CDC and Chapel Complex”**,
 - **“Parade Field”, “Soldier-On Field”**,
 - **“BLDG 6036-Wings Chapel”**,
 - **“Veteran’s Park”**,
 - **“BLDG 6001-TSF”**,
 - **“BLDG 6000-Museum”**,
 - **“BLDG 101-Post HQ”**,
 - **“BLDG 5700-Garrison HQ”**,
 - **“BLDG 4905-Safety Center”**,
- **as identified in TE 2, Historical Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

After mowing the lawn shall be uniform in appearance, free of skips, gaps, rutting, or scalping. The Contractor shall be responsible for any damage incurred because of grass cutting operations.

5.2.3.1 Wet Areas.

Contractor shall use appropriate equipment for current ground conditions and shall repair all damaged areas resulting from utilization of inappropriate equipment for current ground conditions.

5.2.4 Edging.

Edging shall be performed CONCURRENTLY with each mowing.

- The Contractor shall edge to present a neat appearance.
- Edging responsibilities shall include, but not be limited to
 - sidewalks,
 - driveways,
 - street edges, curbs, and other concrete (except against asphalt edges) located in the Improved Grounds.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- Edging shall also include the removal of all grass or weeds sprouting from cracks in
 - sidewalks,
 - pavement, and
 - curb joints.
- The use of post-emergent herbicides by the Contractor, for edging purposes, is limited to grass in cracks and shall not be used to edge the entire area.
- The Contractor shall collect and dispose of all edging debris the same day edging is performed and may be disposed of at the borrow site located on Fort Rucker main post.
- **Ground Cover :**
 - Contractor shall edge all curbed beds that contain ground cover, and all sidewalks adjacent to ground cover, **and shall also remove weeds, bushes, vines, and all other foreign growth that is not existing ground cover, concurrently with each mowing.**

5.2.5 Trimming.

Trimming shall be performed CONCURRENTLY with each mowing.

- The Contractor shall, in conjunction with grass cutting, trim grass and weeds around trees, shrubs, buildings, fences, poles, posts, fire hydrants, parking lot bumper blocks, boulders, and all other fixed objects that project above the ground so grass height is maintained consistent with adjacent grass.
- The contractor shall also **remove** (cut) any small trees less than 4 inches in diameter and saplings, vines and any vegetation that is growing in, on and/or through fences and cable barriers.
- The contractor shall remove **any** dead, or dying, shrubs and bushes by cutting the plants off at ground level and disposing of the plant material.
- **The use of herbicides by the Contractor shall be limited to the post perimeter fence line and for use in preventing grass growth on sidewalks.**
- The Contractor shall remove all trimming debris from sidewalks and driveways on the same day trimming is performed and may be disposed at the borrow site located on Fort Rucker main post.
- The Contractor shall repair any damages to trees and shrubs caused by trimming.
 - **If a plant is damaged by trimming and dies or becomes unhealthy, the Contractor shall replace the damaged plant with a plant of the same size and type at no additional cost to the Government.**
 - **The Contractor shall provide a one (1) year warranty on all replacement trees and shrubs.**

5.2.6 Fertilizing and Liming.

The Contractor shall apply commercial, N-P-K granular fertilizer (13-13-13 @ 300 LB/AC) and/or pulverized agricultural lime (2 TON/AC) to areas as ordered.

5.2.7 Weed Control.

Herbicide application shall be limited to **Railroad Rights-of-Way**, parade fields and athletic fields or locations as approved by the COR.

- Contractor personnel that apply herbicide shall have an appropriate State of Alabama herbicide application certificate or license for the type of work being accomplished.
- The Contractor shall ensure training and licenses and/or certificates of Contractor personnel are kept current.
- The Contractor shall provide copies of these licenses or certifications to the Contracting Officer (KO), not later than (NLT) ten (10) calendar days after the phase-in period has started, and again within ten (10) calendar days upon a change in personnel. (**See Deliverables Schedule, TE 8.8 Deliverable 22**)
- The Contractor shall submit a consolidated list of all chemicals used during the month, in a monthly herbicide application record to the COR/ACOR. (**See Deliverables Schedule, TE .88 Deliverable 23**)
- All mixing and storage of herbicide shall be performed off the installation.
- If the Contractor spills or releases any hazardous substances, *i.e.*, substances listed in 40 CFR 302, *Designation, Reportable Quantities, and Notification*, the Contractor shall immediately notify the KO, followed by written notification within one (1) hour. (**See Deliverables Schedule, TE 8.8 Deliverable 24**)
- The Contractor shall submit a herbicide usage report of all herbicides use to the KO **within one (1) day after application of any herbicide.** (**See Deliverables Schedule, TE 8.8 Deliverable 25**)

5.2.8 Remove Debris, Leaves, and Litter.

Debris and Litter patrol shall be performed CONCURRENTLY with each mowing. The Contractor's responsibilities shall include, but not be limited to:

- the removal and disposal of all natural debris, (*e.g.*, tree limbs less than 4 inches in diameter, rodent habitats, etc.) litter, and trash.
- Leaves shall be removed from BLDG 5700 and BLDG 101 concurrently with each mowing. This includes all areas within the boundary defined in the TE's, **except** for parking lots.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- Leaves along with organic debris such as grass clippings, tree trimmings, and pine straw shall be removed from all other High Visibility Areas (Improved Areas), **as ordered** by the KO/COR.
- Natural debris such as tree limbs, grass clippings, brush, leaves, and other organic waste shall be disposed of at the borrow site located on Fort Rucker main post.
- Trash such as glass, bottles, cans, paper, and such shall be deposited off the Installation the same day it is collected.

5.2.9 Tree Pruning – Crepe Myrtle.

During **DECEMBER of each year**, the Contractor shall trim all tree limbs which are damaged, unsightly, or present unsafe conditions and remove all associated debris. Pruning shall be accomplished IAW (latest editions)

- ANSI A300 (Part 1)-2017, *Tree, Shrub, and Other Woody Plant Management – Standard Practices (Pruning)* and
- ANSI Z133-2017, *Arboricultural Operations - Safety Requirements*, or the most current approved update and
- ANSI A300, *Tree, Shrub and Other Woody Plant Management – Standard Practices (Pruning)*, or the most current approved update and
- ANSI *Third Edition, Best Management Practices – Tree Pruning -2019* and
- National Arborist Association standards.
- General location and count of Crape Myrtles are identified in **TE 8.2 to TE 8.4, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**
- Natural debris such as tree limbs, clippings, brush, leaves, and other organic waste may be disposed of at the borrow site located on Fort Rucker main post.

5.2.10 Hedge and Shrub Maintenance.

The Contractor shall maintain shrubs and other plants to maintain their natural growth characteristics to enhance the beauty and health of the plant.

- Hedges and shrubs shall be free of dead limbs.
- Hedge trimming shall be performed IAW the Work Capability Levels table.
- All clippings, branches and debris resulting from hedge and shrub trimming and pruning shall be removed the same day work is accomplished.
- Shrubs and other plants shall be pruned as required to maintain a **MINIMUM TWELVE (12)** inch clearance from buildings, sidewalks or other obstructions.
- **Pruning of shrubs shall be once in MAY and once in SEPTEMBER.**

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- General locations of hedges and shrubs to be maintained are located within the areas identified in **TE 8.2 to TE 8.4, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

5.2.10.1 Dead Shrubs and Other Plants:

When the contractor encounters dead shrubs, bushes and other dead plants in the accomplishment of **mowing or pruning**, the dead shrubs and other plants shall be removed by cutting off at ground level and removing the dead plant material.

5.2.11 New Ammo Storage Point (ASP) Area.

- The contractor shall maintain a “clear zone” of 20 feet out from the ASP perimeter fence.
- The eleven (11) grass covered ammo storage bunkers shall **ONLY** be mowed once every 2 months to reduce erosion and rutting of the earthen cover.

5.2.12 Special Services.

The Contractor shall provide additional services as necessary due to unforeseen circumstances, including but not limited to, Very Important Person (VIP) visits, retreats, ribbon cutting ceremonies, and open houses.

- The Contractor shall provide extra labor and equipment to service pre-identified locations within the High Visibility and Common Areas beyond the normal grounds maintenance.
- The COR/ACOR will notify the Contractor of special service requirements NLT forty-eight (48) hours prior to the event.
- The Contractor shall coordinate special service requirements with the existing grounds maintenance schedule.

5.2.12.1 Special Event Services.

Upon receiving direction from the COR/ACOR, the Contractor shall complete work prior to the event.

- In the event the Contractor must deviate from their schedule to meet special event requirements, the Contractor shall do so at no additional cost to the Government.
- The Contractor shall be authorized/entitled one (1) additional duty day to return to their normal operations.
- Furthermore, the Contractor will not be held accountable for any unsatisfactory performance results, on a quality assurance inspection or

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

complaint, due to KO-directed schedule change(s), until such point when the Contractor resumes normal operations.

5.3 Service Common Areas – TE 8.5 (Semi-Improved Grounds).

Semi-Improved Grounds used for operational and maintenance purposes. Erosion control shall be the predominant grounds maintenance work performed in this area by the Contractor. Common Areas, approximately 240 acres, are indicated in **TE 8.5, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

- **Trimming and debris removal shall be done concurrently with mowing.**
- Roadways shall be cut and trimmed from the road edge to the tree line or fence line.
- Grass to be maintained **IAW TE 8.10, Work Capability Levels and TE 8.5.**
- Railroad rights-of-way shall have four scheduled applications of herbicide to eliminate any vegetation in the track ballast areas.

5.3.1 Trimming, See paragraph 5.2.5 Trimming, above

5.3.2 Remove Debris, Leaves and Litter, See paragraph 5.2.8 Remove debris, Leaves and litter, above.

5.3.3 Herbicide Application to Railroad Rights-Of-Way.

- Grounds maintenance in this area shall consist of four (4) seasonally-timed herbicide applications of a glyphosate product.
- Applications shall be to track ballast averaging sixteen (16) feet in width along the length of all tracks identified in **TE 8.5, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**
- The approximate number of acres to receive herbicide treatments is 4.5 acres, each application.
- These applications are designed to eliminate vegetation growing on the right-of-way ballast.
- Herbicides applications shall be made with ground application equipment as a liquid spray.

The Contractor will determine the timing of applications and submit to the COR for approval 5 workdays prior to application. See Deliverables Schedule, TE 8.8 Deliverable 26

5.3.3.1 Herbicide Approval

All pesticides (including herbicides) used on the installation must be registered with the EPA and the applicable State of Alabama lead agency (ADEM) for the

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

intended use. Products proposed for use on Fort Rucker must also be approved for use on Fort Rucker prior to purchase or transport onto the installation. The installation maintains an approved Pesticide Use List (PUP) **(TE 8.9, Approved Herbicides)** that is updated annually. Glyphosate products on this list may be used without other approval excepting that of the COR. Requests to use a glyphosate product not currently listed on the Installation PUP shall be submitted in writing to the KO and COR. Such requests shall be accompanied by the product label and a Safety Data Sheet (formerly MSDS) for any product(s) proposed for use. Such requests will be passed to the Installation Pest Management Coordinator for action and approval. Formal approval is by the Command Pest Management Consultant (Army Environmental Center, Fort Sam Houston, TX) **and can take 7-10 days.**

5.3.3.2 Certification of Applicator Personnel.

Contractor personnel selecting, mixing and/or applying herbicides used in the execution of this contract shall MEET THE CERTIFICATION REQUIREMENTS AS SPECIFIED IN AR 200-1 ENVIRONMENTAL PROTECTION AND ENHANCEMENT, AND DODI 4150.7 SECTION E3.3 REFERENCED THEREIN (at a minimum be State of Alabama certified in the operational category ROW (Right-of-Way Pest Control)).

- Contractor's shall submit all required federal, state, and local licenses and/or certifications as part of the solicitation to the KO or COR prior to any onset of chemical applications. **(See Deliverables Schedule, TE 8.8 Deliverable 27).**
- Contractor shall also submit applicators resume containing his/her name, educational background, employment history, periods of employment, title, experience history (where, when, duties, level of responsibility, title), and employment status with this company. **(See Deliverables Schedule, TE 8.8 Deliverable 28).**

5.3.3.3 Dispersal Equipment.

Spray equipment shall be capable of rapid spray delivery and provide specialty low drift nozzles.

- All tanks, hoses, pumps, control valves, and gauges shall be free of visible deterioration, shall not leak, and shall operate at the manufacturer's recommended rates and pressures.
- Equipment that has failed shall be repaired and/or replaced by the Contractor prior to initiation or resumption of operations.

5.3.3.4 Storage and disposal.

Bulk pesticide storage on the installation is not permitted.

- Working stocks of the herbicide(s) to be used under this Contract shall be maintained in locked storage compartments carried on Contractor vehicles and shall be removed from the installation at the end of each workday.
- Disposal of empty pesticide containers shall be in accordance with applicable EPA, ADEM, and local regulations, laws, ordinances and policies.

5.3.3.5 Reporting.

The Contractor shall maintain daily records of all herbicide applications including weather data and observations.

- The Contractor shall be responsible for reporting herbicide applications, surveillance inspections and accidental spill or discharge events as required by Fort Rucker's NPDES permit.
 - Specific reports required for each application under the specifications of this contract include
 - completed AVCOE Form 2740 Pest Management Maintenance Record;
 - AVCOE Form 2743 Pest Management Monitoring;
 - and AVCOE Form 2744 Pesticide Corrective Actions (if required as the result of an incident).
 - Required forms and instruction timelines for completing and filing those forms are available at:
 - [Sustainable Fort Rucker \(fortRucker-env.com\)](http://SustainableFortRucker.com).

Completed forms shall be provided to the COR within 7 working days of completion of any applications.

5.3.3.6 Spill Prevention.

A spill prevention and clean-up plan shall be submitted to the COR through the KO for approval prior to the onset of any pesticide applications.

- The Contractor is required to have a copy of the approved plan and appropriate spill containment and clean-up equipment, and any required protective clothing and equipment required for clean-up on site during any transport, mixing or application activities.
- If any hazardous material gets on the ground, in a drain or in a waterway it must immediately be reported by dialing 911 and by calling Fort Rucker DPW-ENRD, 334-255-1657 / 1653.

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- The contractor performing this work must have on hand (at the project site) SDS's for all chemicals used as part of this project.

5.3.3.7 Results.

Contractor shall inspect areas sprayed after 14 days to determine the effectiveness of the application.

- Effectiveness shall be determined based on **all** grass, weeds and other vegetation being dead or obviously dying in the area sprayed.
- **Any** areas that are not dead or dying shall be resprayed.
- After all vegetation has died, the dead vegetation shall be trimmed during the next scheduled cutting of the areas where the Railroad track is located.

5.4 Service Unimproved Areas – TE 8.6 (Unimproved Grounds).

Undeveloped areas, grazing lands, forests, lakes, ponds, wetlands, and special natural areas: refuges, natural areas, forests and wildlife corridors where low levels of maintenance are acceptable and visibility is minimal and other areas as identified as Unimproved Grounds.

- Specific unimproved areas that receive grounds maintenance are the perimeter fence line, portions of Lake Tholocco Dam and two capped landfills that total approximately **125 acres**.
- Services provided for Unimproved Areas are identified in the Work Capability Levels table.
- **Grass to be maintained IAW TE 8.10, Work Capability Levels.**
- **The frequency of mowing Unimproved Areas is three (3) times per year and areas are identified in TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

5.4.1 Mowing Unimproved Areas:

- Mowing in unimproved areas is three times annually – **once during the month of March, June and September.**
- Roadways shall be cut from the road edge to the tree line.
- Debris shall be collected prior to cutting.
- **Unimproved areas shall be maintained IAW TE 8.10, Work Capability Levels and TE 8.6 Service Frequencies.**
- **Vegetation shall be trimmed around all obstacles in the area CONCURRENTLY with each mowing.**

5.4.2 Perimeter Fence Line / Cable Barrier, Old Landfill's and Lake Tholocco Dam Maintenance.

5.4.2.1 Perimeter Fence Line / Cable Barrier.

- Work shall consist of the cutting / removal of grass, weeds, vines, trees (less than 4.0 inches in diameter at ground level), and all other vegetation on and/or around the fence or cable barrier to ground or pavement level within **TWENTY (20) FEET** on the exterior side and **FIFTY (50) FEET** on interior side of the fence or cable barrier.
- **Where established tree lines are closer to the fence / cable barrier than the distance established above, then that distance shall be the limits of cut.**
- The area shall be maintained **IAW TE 8.10, Work Capability Levels.**
- Unless otherwise specified in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services**, shall be by mechanical means.
- Frequencies are identified in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

5.4.2.2 Lake Tholocco Dam.

- Work shall consist of the removal of grass, weeds, woody brush, saplings and other vegetation from water line to the banks and locations on the dam as designated and shown in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**
- Removal of woody stems and saplings shall be to ground level and include all stems less than 2 inches in diameter.
- The area shall be maintained **IAW TE 8.10, Work Capability Levels.**
- Unless otherwise specified in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services**, shall be by mechanical means.
- Frequencies are identified in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

5.4.2.3 Old Landfill's.

Work shall consist of the removal of grass, weeds, trees (less than 4.0 inches in diameter at ground level), and all other vegetation on the site as designated and shown in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services.**

- The area shall be maintained **IAW TE 18.0, Work Capability Levels.**

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

- Unless otherwise specified in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services**, shall be by mechanical means.
- Frequencies are identified in **TE 8.6, Service Frequencies, Grounds Maintenance Inventory and Grounds Maintenance Services**.

5.4.3 Remove Debris, Leaves and Litter, See paragraph 5.2.8 Remove debris, Leaves and litter, above

5.5 Other Special Services.

5.5.1 Special Equipment Requirements.

5.5.1.1 All rotary mowers used within High Visibility Areas (Improved grounds) shall be equipped with mulching blades and have discharges blocked.

5.5.1.2 All equipment used to perform grass mowing and leaf removal operations on High Visibility (Improved Grounds) Areas shall be equipped with turf type tires.

- Equipment not essential for the performance of grass mowing or leaf removal functions (e.g., equipment with agricultural tires, wheel weights, snow blades, or other accessories that may damage turf or tree root zones by compaction, rutting, or scalping), shall not be permitted on High Visibility Areas.

5.5.1.3 Contractor shall use appropriate equipment for current ground conditions and shall repair all damaged areas resulting from utilization of inappropriate equipment for current ground conditions.

5.5.1.4 The Contractor shall submit a complete equipment list including number, age, make, model, specifications and catalog cut sheets with the proposal. (**See Deliverables Schedule, TE 8.8 Deliverable 29**).

PART 6 APPLICABLE PUBLICATIONS

6.0 Applicable Publications (Current Editions).

Publication Sources include but are not limited to DoD Issuances (<https://www.esd.whs.mil/DD/DoD-Issuances/>); Army Publishing Directorate (<https://armypubs.army.mil/>), Code of Federal Regulations (<https://www.ecfr.gov/>) and Federal Acquisition Regulations (<https://www.acquisition.gov/>).

6.1 Regulations, Publications, Manuals, Local Policies and Procedures.

The Contractor must abide by all LOR including but not limited to the following.

ACC PAM 70-1	Interim Army Contracting Command – Contracting Officer's Representative Policy Guide
ANSI Z87.1-2003	Practice for Occupational and Educational Personal Eye and Face Protection Devices
AR 25-2	Information Management: Army Cybersecurity, section 2-34 All personnel, 4-25 Privately owned information technology.
AR 70-1	Army Acquisition Policy
AR 70-13	Management and Oversight of Service Acquisitions
AR 190-13	Army Physical Security Programs, Chapter 5 Security Identification Cards and Badges, Chapter 8 Army Installation and Facility Access Control, Chapter 20 Vehicle control
AR 190-51	Security of Unclassified Army Resources (Sensitive and Non-sensitive), Appendix D Policy for locks and keys
AR 200-1	Environmental Protection and Enhancement, Green Procurement policies.
AR 215-1	Military Morale, Welfare, and Recreation Programs and Non-appropriated Fund Instrumentalities

Ft. Rucker, Al. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

AR 381-12	Threat Awareness and Reporting Program
AR 380-5	Army Information Security Program, 1-14.
AR 420-1	Army Facilities Management, section VI Grounds maintenance Services.
AR 530-1	Operations Security, section 2-22, All Army personnel, to include contractors.
AR 608-10	Child Development Services, section 5-37 Grounds maintenance and housekeeping services
29 CFR Part 1910	Occupational Safety and Health Standards
29 CFR Part 1925	<u>Safety and Health Standards for Federal Service Contracts</u>
40 CFR	Protection of the Environment
40 CFR Subchapter I	Solid Wastes
40 CFR Part 302	Protection of Environment, Designation, Reportable Quantities and Notification
49 CFR 390-396	Motor Carrier Safety Standards
49 CFR 571	Federal Motor Vehicle Safety Standards
CAA	Clean Air Act (CAA)
CWA	Clean Water Act (CWA)
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)
DA PAM 5-20	Competitive Sourcing Implementation
DoDD 5500.7	Standards of Conduct
DoDI 2000.16, Vol. 1	DOD Antiterrorism Standards

Ft. Rucker, AL. Cantonment Grounds Maintenance Services Enterprise-wide
Performance Work Statement (PWS)
(ISR 404 – Grounds Maintenance Services) (U)

DoDI 5000.72	DoD Standard for Contracting Officer's Representative (COR) Certification
DODI 6055.07	Mishap Notification, Investigation, Reporting, and Record Keeping
EM 385 1. 1.	Safety and Health Requirements Manual
EO 14042:	Ensuring Adequate COVID Safety Protocols for Federal Contractors
FAR Part 23.4	Use of Recovered Materials and Biobased Products
Federal Standard #313	Material Safety Data and Disposal Data for Hazardous Materials Furnished to Government Activities
FIPS PUB 201-2	Personal Identity Verification (PIV) of Federal Employees and Contractors
HSPD 12	Homeland Security Presidential Directive 12 Policy for a Common Identification Standard for Federal Employees and Contractors
MEDCOM Reg. 40-35	Management of Regulated Medical Waste
NFPA 1.12-2	Combustible Fibers
OMB M-05-24	Office of Management and Budget (OMB) Guidance Implementation of Homeland Security Presidential Directive (HSPD) 12-Policy for a Common Identification Standard for Federal Employees and Contractors
TB MED 531	Facility Sanitation Controls and Inspections
TM 5-609	Military Grounds maintenance Services Manual

PART 7
FORMS AND REPORTS

7.0 Mandatory Records and Report Forms.

DD or DA Form Sources include but are not limited to: DoD Forms Home
(<https://www.esd.whs.mil/Directives/forms/>); Army Publishing Directorate
(<https://armypubs.army.mil/>)

DA Form 5513	Key Control Register and Inventory
DD Form 200	Financial Liability Investigation of Property Loss (eFLIPL)
DD Form 254	DoD Contract Security Classification Specification
DD Form 577	Appointment/Termination Record
DD Form 1348-1	Release/Receipt Document
SF 85P	Position of Public Trust
SF 701	Activity Security Checklists

PART 8
TECHNICAL EXHIBIT LISTING

8.0 Attachment/Technical Exhibits (TEs).

8.1 Technical Exhibit (TE-1) – Performance Requirements Summary.

SEE ATTACHED

**8.2 Technical Exhibit (TE-2) – Historical Service Frequencies, Grounds
Maintenance Inventory and Grounds Maintenance Services - Area A.**

SEE ATTACHED

**8.3 Technical Exhibit (TE-3) – Historical Service Frequencies, Grounds
Maintenance Inventory and Grounds Maintenance Services - Area B.**

SEE ATTACHED

**8.4 Technical Exhibit (TE-4) – Historical Service Frequencies, Grounds
Maintenance Inventory and Grounds Maintenance Services - Area C.**

SEE ATTACHED

**8.5 Technical Exhibit (TE-5) – Historical Service Frequencies, Grounds
Maintenance Inventory and Grounds Maintenance Services – Semi-
Improved.**

SEE ATTACHED

**8.6 Technical Exhibit (TE-6) – Historical Service Frequencies, Grounds
Maintenance Inventory and Grounds Maintenance Services -
Unimproved.**

SEE ATTACHED

8.7 Technical Exhibit (TE-7) – Historical Temperature and rainfall data.

SEE ATTACHED

8.8 Technical Exhibit (TE-8) – Deliverables Schedule.

SEE ATTACHED

8.9 Technical Exhibit (TE-9) – Approved Herbicides.

SEE ATTACHED

8.10 Technical Exhibit (TE-10) – Work Capability Levels.

SEE ATTACHED

**8.11 Technical Exhibit (TE-11) - General Locations of Internal Fencing and
Cable Barriers, Cantonment Grounds Maintenance Contract.**

SEE ATTACHED

**8.12 Technical Exhibit (TE-12) - Example Payment Calculations When RESD
is Used.**

SEE ATTACHED