

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		PAGE 1 OF 11 PAGES		
2. AMENDMENT/MODIFICATION NUMBER A0002			3. EFFECTIVE DATE 01/27/2026		4. REQUISITION/PURCHASE REQUISITION NUMBER		5. PROJECT NUMBER (If applicable)	
6. ISSUED BY Indian Health Service - DES Seattle 701 5th Avenue, Suite 1600 Seattle, WA 98104			7. ADMINISTERED BY (If other than Item 6)		CODE			
8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)					(X)			9A. AMENDMENT OF SOLICITATION NUMBER
					(X)			75H70126R00009
					(X)			9B. DATED (SEE ITEM 11) 01/05/2026
					()			10A. MODIFICATION OF CONTRACT/ORDER NUMBER
CODE					FACILITY CODE			10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended. ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation data, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

A. The purpose of this amendment is to provide 1) an updated Q&A sheet as of January 27, 2026, and 2) Site Visit Attendee List.

B. The Government is still working on the pending responses and will not accept any further questions or inquiries concerning this RFP.

C. The RFP response date and time was changed from Feb 5, 2026 at 1:00 PM PT to Feb 12, 2026 at 1:00 PM PT.

D. All other terms and conditions of this Solicitation remain unchanged.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
		Andrew Hart, Contracting Officer	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

Pre-Proposal Meeting/Site Visit

DATE: January 16, 2026

TIME: 10:00 AM MT

LOCATION: Participants will meet near the Pine Ridge hospital on the corner of Pejuta Rd and Cougar St.

PROJECT TITLE:

Pine Ridge Multiplex Construction

SOLICITATION NUMBER:

75H70126R000009

CONTRACTING OFFICER:

Andrew Hart

CONTRACT SPECIALIST:

Jong Kim

PROJECT MANAGER:

Stottin Newbrough

ATTENDEES

SIGNATURE	NAME	PHONE	Organization / Title
	Andrew Hart	206-615-2453	Contracting Officer
	Jong Kim	206-619-0638	Contract Specialist
	Stottin Newbrough	605-945-5452	Project Manager (PM) / COR
<i>Andy Zilve</i>	Andy Zilve	701-951-9715	Greenstone Construction
<i>Tyler Walker</i>	Jim Demarais	701-612-1533	Greenstone Construction
	Tyler Walker	605-391-4056	TATCo Construction Services
	Fred Langan	719-320-3845	Tepa
	Bruce Allen	605-997-5003	Allen Construction Company
	Darby Landgren	605-997-5003	Allen Construction Company
<i>[Signature]</i>	Richard Smith	623-271-0384	Diamond West
<i>[Signature]</i>	Josiah Scull	605-342-3787	RCS Construction
<i>[Signature]</i>	Calvin Ghost Bear	605-381-0823	Ghost Bear Contracting
<i>[Signature]</i>	Herb Schmitt	605-381-0823	Dean Kurtz Construction
<i>[Signature]</i>	Curtis Boschult	402-922-2807	Lacreme Construction
	PJ Marthon	509-907-5809	RJS/Blackrock
	Dan Johanneson	509-907-5809	Johanneson Contracting
	Issac Francis	509-907-5809	Precision Grading
	Will Freeman	509-907-5809	Heartland Drywall and Painting
<i>[Signature]</i>	<i>Chris Olson</i>	<i>605-655-7449</i>	<i>Lacreek Drywall</i>
<i>Mitch Sisco</i>	Mitch Sisco	918-207-8273	TSR

Chris Stewart 970-959-0017 *Razon*
Eddie Bissonette 605-484-6311 *TATCo*
Tony Ward 605-685-5772 *Sods mechanical*

Amend No.	Item #	Date Submitted	Question Type (Technical or Admin)	Question	Response Date	Response	Responded By
EXAMPLE	0	11/23/2020	Technical	Please provide drawings or plans for ???	11/23/2020	IHS Response	IHS POC
A0001	1	1/12/2026	Admin	Please confirm that the RFP reference on page 32 of 54, Section H, H.48, (c), is correct and not a misprint. We are assuming the Northern Cheyenne Tribe that is referenced is in Montana.	01/14/2026	It was changed from Northern Cheyenne Tribe to Oglala Sioux Tribe.	IHS CS
A0001	2	1/12/2026	Technical	The project documents state a Geotech Report would be attached but we cannot locate it. Would you please release this document?	01/14/2026	The Geotech Report is being provided by Amendment A0001	IHS COR
	3	1/15/2026	Technical	Can pex A pipe and fittings be used?			A/E
	4	1/15/2026	Technical	Can manifolds for DW be used?			A/E
	5	1/15/2026	Technical	Can we get a specific countertop manufacturer and color selection specification? The spec section identifies three solid surface manufacturers with a note to cover the full line, which has a very wide cost range. Also, note that due to the size of the islands there will be a seam and the waste will be significant. We would like to propose using an import or domestic quartz or granite material instead of the solid surface material. Is that acceptable?			A/E
	6	1/16/2026	Technical	Can we use Viega ProPress copper fittings?			A/E
	7	1/19/2026	Technical	Please reference drawing sheet S101 and S501. Foundation plan indicates interior walls that show full height interior walls and footings. Can these be changed to thickened slab interior walls poured integrated with the SOG?			A/E
	8	1/20/2026	Technical	Reference drawing sheet A201. Please confirm masonry veneer height is 4'-0" and not 2'-4" as indicated. the 2'-4" dimensions does not make sense nor does it scale correctly with the drawings.			A/E
A0002	9	1/20/2026	Technical	Will IHS accept the use of Procore Project Management software as the primary submittal and Project management platform?	01/23/2026	Yes.	IHS COR
A0002	10	1/20/2026	Technical	Can you provide the location of parking and staging area assigned to this project?	01/23/2026	Near the site.	IHS COR
A0002	11	1/20/2026	Technical	Can the prebid site visit attendees sign in sheet be provided?	01/23/2026	Yes, it is being provided by Amendment A0002.	IHS CS
	12	1/20/2026	Technical	Is their any seismic design requirements required for this project?			A/E
A0002	13	1/20/2026	Technical	013100 – 1.7 RFI's can you provide the review period for RFI's including VA, A/E and any consultants review in days?	01/23/2026	Not sure what this RFI is asking.	IHS COR
A0002	14	1/20/2026	Technical	013233 Photographic Documentation 1.4 A Photographer: Engage a qualified photographer to take construction photographs. Can the photos be taken by our project Superintendent?	01/23/2026	Yes.	IHS COR
A0002	15	1/20/2026	Technical	013300 Submittal Procedures 1.4C states that the submittal review time is 14 calendar days, does this duration include the VA, A/E and any consultants?	01/23/2026	Who is the VA? Review team will be IHS COR/PM and A/E if needed.	IHS COR
	16	1/20/2026	Technical	013300 1.7 Delegated Design can you provide any required delegated design systems required by contractor?			A/E
A0002	17	1/20/2026	Technical	014000 1.6 B Contractors Quality Control Staff - Can the Quality Control Supervisor also serve as the superintendent?	01/23/2026	Yes.	IHS COR
	18	1/20/2026	Technical	014000 1.7 B Tests and Inspections can you provide the government test / inspections that will be performed by HIS.			A/E
	19	1/20/2026	Technical	014000 1.8 Special Tests can you provide the required special tests the contractor is required to perform?			A/E
	20	1/20/2026	Technical	019113 – 1.4 B can you confirm the Government will engage or hire the CxA under a separate contract?			

A0002	21	1/20/2026	Technical	024119 – 3.3 can you clarify if there are any items that will be salvaged and turned over to IHS?	01/23/2026	New construction. Extra building material can be left with IHS.	IHS COR
	22	1/20/2026	Technical	030130 – Maintenance of cast-in-place concrete specification can you provide the location of the deteriorated concrete required to be removed? As it is not indicated in the plans			A/E
	23	1/20/2026	Technical	Can you provide the specification requirements for the Precast concrete caps and sills indicated on top of the masonry walls?			A/E
	24	1/20/2026	Technical	061613 – 2.2 can you confirm the use of R-6 ZIP system sheathing panels for the exterior wall sheathing?			A/E
	25	1/20/2026	Technical	061600 – 2.2 can you provide the specification requirements for the roof sheathing materials			A/E
	26	1/20/2026	Technical	061000 Rough Carpentry 2.3 Fire-Retardant Treated Materials E – Can you define the locations of treated materials for clarity i.e. sill plate, Interior Wood Blocking, Clarify the roof structure treated components required, etc. are their other locations required?			A/E
	27	1/20/2026	Technical	061600 Sheathing 2.2 Wall Sheathing A identifies Glass-Mat Gypsum Sheathing the plans indicate R6- Zip Sheathing in the wall section on detail 3 on sheet A311 can you please clarify which product is required for the exterior wall sheathing and provide appropriate specifications?			A/E
	28	1/20/2026	Technical	072100 -3.2 can you clarify the foundation insulation is required to extend 24" wide horizontally as the wall section details do not indicate the horizontal area is required?			A/E
A0002	29	1/20/2026	Technical	085313 -2.2 Vinyl Windows can Pella be an approved manufacture	01/23/2026	Yes.	IHS COR
	30	1/20/2026	Technical	Section 096519 2.2 products identified in specifications include Armstrong Theorem, Shaw Floorte and Mohawk Solidtech, Theorem is a glue down, Floorte & Solidtech are floating floors. The flooring installer recommends to use a glue down product. Can you review the products and clarify the type of floor to use?			A/E
A0002	31	1/20/2026	Technical	099113 – 3.5 Exterior Painting Is the LP siding to receive field painting or is the LP siding a Factory Finish can you clarify?	01/23/2026	Factory finished. Color selected during the submittal phase.	IHS COR
	32	1/20/2026	Technical	101423.16 2.2 Can you provide a sign schedule and the graphics for the exterior aluminum panel sign?			A/E
	33	1/20/2026	Technical	104416 – 2.2 Can you provide locations of Fire Extinguishers on the plans?			A/E
A0002	34	1/20/2026	Technical	113013 – 2.1 Residential Appliances can you clarify if we a required to supply the Fridge, Washers, Dryers if so can you provide the specifications for these items?	01/23/2026	This project does not include the procurement of residential appliances. Any government purchase of such appliances would be handled under a separate project.	IHS CS
A0002	35	1/20/2026	Technical	113013 -2.1 Are we required to unload, assembly, and install owner supplied appliances?	01/23/2026	No.	IHS COR
A0002	36	1/20/2026	Technical	Sheet A3.1 Can you clarify the window sills are a sheetrock return?	01/23/2026	Yes.	IHS COR
	37	1/20/2026	Technical	Can you provide support backing details and material requirements for wall mounted accessories including the grab bars and shower seats to support 250 lb. as indicated in section 102800 Toilet and Bath Accessories.			A/E
	38	1/20/2026	Technical	061600 Sheathing Subfloor Sheathing can you define the appropriate materials for the Subfloor sheathing and update the specifications for section 2.2			A/E
	39	1/20/2026	Technical	The Room Finish Schedule noted the floor base to be wood - Specification section 096513 Resilient Bas & Accessories indicates Rubber Base. Can you clarify if wood base is required and remove section 096513 from this scope.			A/E

A0002	40	1/20/2026	Technical	Section 122413 Roller Window Shades 1.2 B 1 Submittals indicate motor-operated shades can you clarify if motor shades are required?	01/23/2026	No. Manual shades.	IHS COR
	41	1/20/2026	Technical	Sheet C200 indicates a retaining wall can you provide the specifications for retaining wall?			A/E
	42	1/20/2026	Technical	The interior wall types B1,B2 and C indicate metal stud walls, can you provide a comparable wood stud wall design as an option in lieu of wood?			A/E
	43	1/20/2026	Technical	The plans indicate a mop sink shelf can you provide specifications for this product			A/E
	44	1/20/2026	Technical	The plans indicate FRP panels can you provide specifications for this product			A/E
	45	1/20/2026	Technical	The plans indicate steel pipe bollards can you provide specifications for this product			A/E
	46	1/20/2026	Technical	The plans indicated aluminum gates can you provide specifications for this product			A/E
A0002	47	1/21/2026	Admin	Will the government please extend the bid deadline by a minimum 21 calendar days from when all RFI responses are received so that KTR can incorporate government responses into the proposal and price accordingly?	01/27/2026	The Government acknowledges the request to extend the proposal submission deadline by a minimum of 21 calendar days following the release of all RFI responses. The Contracting Officer will determine whether an extension is necessary based on the nature of the RFI responses and overall acquisition needs. If an extension is deemed necessary, the Government will issue an official amendment to the solicitation to revise the proposal due date. Offerors should continue to prepare and submit proposals in accordance with the solicitation as currently written unless notified otherwise through an amendment.	IHS CS
A0002	48	1/21/2026	Technical	The Period of Performance is not long enough for review and approval of government required submittals, procurement of long lead materials and equipment and or onsite construction. Can the Period of Performance be extended?	01/23/2026	730 POP days.	IHS COR
A0002	49	1/21/2026	Technical	Can the Superintendent perform a dual role? For example, can the Superintendent also be the SSHO?	01/23/2026	Yes.	IHS COR
A0002	50	1/21/2026	Technical	Can the QC Manager perform a dual role? E.g. QC/Superintendent or QC/SSHO.	01/23/2026	Yes.	IHS COR
A0002	51	1/21/2026	Technical	Will the government require the contractor provide an onsite office trailer? Or is it at the contractor's discretion?	01/23/2026	At the discretion of the contractor.	IHS COR
A0002	52	1/21/2026	Technical	Please indicate acceptable laydown/staging areas?	01/23/2026	Near the site.	IHS COR
A0002	53	1/21/2026	Technical	Please indicate acceptable haul routes.	01/23/2026	Pejuta Rd.	IHS COR
A0002	54	1/21/2026	Technical	Will onsite stockpiling be allowed?	01/23/2026	Near the site. Security and storage are the contractor's responsibility.	IHS COR
A0002	55	1/21/2026	Technical	Please provide any available soils reports.	01/23/2026	See item #2.	IHS COR
A0002	56	1/21/2026	Technical	Please provide any available boring logs or Geotech reports for the project.	01/23/2026	See item #2.	IHS COR
A0002	57	1/21/2026	Technical	Please advise if there are any environmental or HAZMAT concerns in any of the areas where work will take place.	01/23/2026	None.	IHS COR
A0002	58	1/21/2026	Technical	Will the reuse of contaminated soils be allowed if encountered? (including within utility trenches)	01/23/2026	No.	IHS COR

A0002	59	1/21/2026	Technical	It is not clear in the RFP whether CERCLA requirements will be applicable to this project. Please advise.	01/23/2026	No.	IHS COR
A0002	60	1/21/2026	Technical	Will KTR be required to do confirmation sampling for areas included in the RFP Provided Hazmat report?	01/23/2026	No. Which HazMat report?	IHS COR
A0002	61	1/21/2026	Technical	Will an NPDES permit be required?	01/23/2026	No.	IHS COR
	62	1/21/2026	Technical	Please advise whether a Storm Water Pollution Prevention Plan will be required for this project.			A/E
A0002	63	1/21/2026	Technical	Will any of the work areas on this project require escorts for access?	01/23/2026	No.	IHS COR
A0002	64	1/21/2026	Technical	Will the government provide escorts for any restricted areas?	01/23/2026	No. Outside work.	IHS COR
A0002	65	1/21/2026	Technical	Please advise if there are any costs for government provided escorts.	01/23/2026	No.	IHS COR
A0002	66	1/21/2026	Technical	Please provide a full set of as-builts for the project.	01/23/2026	Provided.	IHS COR
A0002	67	1/21/2026	Technical	Will the KTR be responsible for all utility costs if temporary utilities are required?	01/23/2026	Yes.	IHS COR
A0002	68	1/21/2026	Technical	Please provide the going rates for temporary utilities.	01/23/2026	Unknown. Contractor to contact the utility companies. Nebraska Public Power. OST Water and Sewer.	IHS COR
A0002	69	1/21/2026	Technical	Will KTR be responsible for any costs associated with base facilities support where and when required for the project?	01/23/2026	Unsure of what this question is asking.	IHS COR
A0002	70	1/21/2026	Technical	Please provide rates for government utility support workers and crew makeup for shutoffs, outages etc.	01/23/2026	Unknown.	IHS COR
A0002	71	1/21/2026	Admin	Please confirm this project does not require compliance with the Buy America Act and that compliance with the Buy American Act is acceptable. NAICS Clarification: SF1442 states 236116 / \$45M size standard; Section L.12 references 238290 / \$22M. Please confirm which applies to this procurement.	01/27/2026	Buy American Act (BAA) compliance is required. The NAICS Code and Size Standard in Section L.12 are typo. It should be NAICS Code 236116, size standard \$45 million.	IHS CS
	72	1/21/2026	Technical	Utility Tie-Ins: Please confirm all existing tie-in points, capacities, and whether utility outages are permitted (including required notice durations).			A/E
A0002	73	1/21/2026	Technical	Owner-Furnished Items: Are there any OFCI/OFOI items (appliances, meters, specialty devices)? If so, what are the GC's responsibilities for receipt, storage, and installation?	01/23/2026	No, new construction.	IHS COR
A0002	74	1/21/2026	Technical	Site Access & Logistics: Please confirm site access constraints, laydown areas, contractor parking, and any security screening or badging requirements.	01/23/2026	See item 52, 53, 54.	IHS COR
A0002	75	1/21/2026	Technical	Inspection & Testing: Are there any special inspection, third-party testing, or commissioning requirements beyond typical?	01/23/2026	No.	IHS COR
A0002	76	1/21/2026	Admin	Bonding: Are there any agency-specific bond form or surety requirements beyond FAR? Please reconfirm the 10-day post-award bonding deadline shown on SF1442.	01/27/2026	There are no agency-specific bond forms or surety requirements beyond those required by the Federal Acquisition Regulation (FAR) and the solicitation. The Government further reconfirms that the successful Offeror shall submit the required performance and payment bonds within 10 calendar days after award, as indicated on SF 1442.	IHS CS
A0002	77	1/21/2026	Admin	Site Visit: Please confirm the January 16 at 10:00 AM MT meeting location (Pejuta Rd/Cougar St) is still accurate following Amendment A0001.	01/27/2026	Yes. The site visit was already held on Jan 16, 2026.	IHS CS

A0002	78	1/21/2026	Admin	Submission Format: Please confirm any required file naming conventions and file size limitations for email submissions.	01/27/2026	See Section L.10.	IHS CS
A0002	79	1/21/2026	Technical	Winter Conditions: Are winter conditions and seasonal limitations anticipated, and does the Government have any required schedule milestones beyond the 730-day period of performance?	01/23/2026	The POP is 730 days. All outdoor work should be scheduled for completion during the warm season, while indoor work should be completed during the cold season.	IHS COR
	80	1/21/2026	Technical	The roof slope is listed as 4:12 on the architectural drawings, but as 5:12 on the structural drawings. Please confirm which roof slope to bid.			A/E
A0002	81	1/22/2026	Technical	Section 013100: 1.10; A speaks to Contractors Permits and Responsibilities. Has the Fire Marshall permit been procured by Indian Health Service ?	01/23/2026	Fire marshall not permitted. Local AHJ and A/E will inspect.	IHS COR
	82	1/22/2026	Technical	Section 030130: 1.1;A & 2.2 speaks to Maintenance of Cast in Place Concrete. Is the section referencing the Contractors new work(s) ? The drawings do not demonstrate existing areas which require the Contractors efforts ?			A/E
	83	1/22/2026	Technical	Section 042613: 2.6; C- 2 speaks to the rainscreen drainage mat being Zip System Rainscreen. Is a system 'as equal or better' acceptable ?			A/E
	84	1/22/2026	Technical	Section 077253:2.1; A speaks to a 'delegated design' engaging a qualified professional engineer to design the rail type Snow Guards. Will the manufacturers submittal containing the design criteria required meet the performance requirements ?			A/E
	85	1/22/2026	Technical	Section 085313: 3.3; A & B speaks to Field Quality Control Testing performance and testing. Will the Aluminum Framed Storefront installer be acceptable to perform testing and report appropriately ?			A/E
	86	1/22/2026	Technical	Section 089119: 2.2; A speaks to the fixed extruded aluminum louvers, naming Aire Technologies Inc. Is a manufacturer providing 'as equal or better' acceptable ?			A/E
	87	1/22/2026	Technical	Hardware Groups are listed on Plan Sheet A601. Is there a specification section (087100) forthcoming? All Hardware to be provided by section 087100 with installation by 084313.			A/E
	88	1/22/2026	Technical	Reference Section 084313 (Aluminum Framed Entrances) 1.3.D & 2.2.A refer to Delegated Design Submittal requirement for this project. This design data is expensive for a project that incorporates a small handful of door/frame openings. Please verify if manufacturers standard test reports are sufficient in lieu of the design analysis.			A/E
	89	1/22/2026	Technical	Reference Section 084313 (Aluminum Framed Entrances) 1.7.A refers to a 10 Year Material and Workmanship Warranty requirement. A standard workmanship warranty of One (1) is can be provided with additional costs for a Two (2) year warranty. The 10 Year warranty cannot be provided. Please confirm a One (1) year warranty is acceptable as detailed in Section C (Statement of Work), Item 2.B. Warranty.			
	90	1/22/2026	Technical	Reference Section 084313 (Aluminum Framed Entrances) 3.3 refers to Field Quality Control incorporating various tests; Water-spray and Air. This project consists of only Aluminum Doors/Frames; no storefront or curtain wall windows/framing. Typically, the Owner is responsible for the initial testing, per 014000, with sub-contractor incurring costs for failures. Being these are door systems; we do not see the need for this Field Quality Control in our proposal.			A/E
	91	1/22/2026	Technical	Reference Section 084313 (Aluminum Framed Entrances) This section does not include a basis of design for either the storefront systems or doors (2.3). Please confirm the basis of design for the Storefront and the Doors, i.e., 451T Storefront and 500 Series Wide Stile Door systems , based upon Kawneer systems. If the basis of design is other than these, please confirm systems			A/E
	92	1/22/2026	Technical	Please reference sheet A111, specifically wall details. They indicate wood studs being built on top of metal studs. Please note stud dimensions from metal to wood will be different. We are assuming this is incorrectly labeled and all framing shall be completely with 3 1/2" or 5 1/2" wood stud lumber. See attached for the drawing sheet detail and reference.			A/E
	93	1/22/2026	Technical	Please note sheet A112, roof plan. There is a note indicating a draftstop required between rooms. Can you please provide a detail or cut section on what this will look like? Material to be used? Sheathing, gypboard, etc?			A/E

	94	1/22/2026	Technical	Spec indicates waterproofing on the foundation walls, but with this project not having a basement it doesn't make sense. Also there is a detail indicating drainage tile at the footing. If this project had a basement area that tile would make sense, but it is a shallow foundation detail. Can you please clarify. See attached for specification reference and drawing detail sheet.			A/E
	95	1/23/2026	Technical	It appears there is a tile section in the spec's, not sure where the tile goes. The Finish Plan only shows LVP.			
	96	1/23/2026	Technical	On Plan A411 what looks like there might be tile for the Surrounds, not sure since it does not list any tile on the elevations for the surrounds.			
	97	1/23/2026	Technical	In the Specs, there are 3 products called out for LVP, which one do you want to use?			
	98	1/23/2026	Technical	The units, what floor threshold are they using at the Doorways into the units.			
	99	1/23/2026	Technical	As for the signs is there a list of rooms? Is there any exterior signage?			
	100	1/23/2026	Technical	Please clarify how the specified snap-on panel is intended to comply with the 20-year weathertight warranty requirements. If the specified panel cannot meet this requirement, please advise whether a mechanically seamed panel (UC-3) is to be provided.			
	101	1/23/2026	Technical	On Drawing Sheet C200 Overall Site Plan there is a reference to "Proposed Duplex Sites" adjacent to the project location of the new multiplex. Please advise if this is for future planning purposes only and that area could potentially be used as laydown/storage?			
	102	1/23/2026	Technical	Drawing Sheet A112 Reflected Ceiling and Roof Plan - Detail 2 has a Note: 5/8" Gypsum Board Ceilings Throughout Building. As well as another note to Provide two (2) layers of 5/8" GYP. BD. At Electrical Room Ceiling. The Specification Section 092900 Part 2.3.B only references Gypsum Ceiling Boards to be 1/2 inch. There are wall details within the drawing set but there are not details that show the connection or type of material used at the ceiling besides the notes on sheet A112. Please advise if 5/8" GYP. BD. should be used throughout, with two layers at location noted, or if it should be 1/2" GYP. BD.?			
	103	1/23/2026	Technical	Solicitation Section H.6.(b) references Project Manager, Superintendent, and Safety Office as required Key Personnel. Further, in section H.8. Superintendent On Site is the only personnel referenced to be required on site. The Specification Section 01.40.00 Part 1.6.B.1 advised that the Quality Control Supervisor may also perform other duties. Is the Superintendent and Safet Officer the only personnel Required onsite during construction with one of those individuals being able to provide QC Supervisor activities onsite during construction?			
	104	1/23/2026	Technical	Drawing Sheet A411 Enlarged Plans and Interior Elevations contains Keynote legend items 11.02, 11.03, 11.04, 11.05, 11.06, 11.07, 11.08, and 11.09 all reference appropriate residential Oven/Ranges, Refrigerators, Microwave/Hood, Dishwasher, or Accessible items that are similar. However Specification Section 113013 Residential Appliances only references generic LG manufacturer for Part 2.2 Ranges, 2.3 Microwave Ovens, and 2.4 Dishwashers. There is not a reference to a refrigerator within the specifications. Using item 11.02 from the drawings and Part 2.2 from the specifications, there are several LG products that could be selected ranging from \$700.00 to \$3,000.00. Please advise if there is a model or additional descriptions for each item or approved equal: Range/Oven, Microwave, Dishwasher, and Refrigerator?			
	105	1/23/2026	Technical	Specifications Section 019113 Part 1.4.B.1 CxA: The designated person, company, or entity that plans, schedules, and coordinates the commissioning team to implement the commissioning process. The Government will engage the CxA under a separate control. Please confirm that the contractor is only to provide commissioning support throughout the project?			
	106	1/23/2026	Technical	The Division of Safety and Risk Management (DSRM) reviews was not identified or referenced within solicitation, will DSRM perform any reviews of delegated design or onsite inspections ?			
	107	1/26/2026	Technical	The geotechnical report does not clearly indicate the required depth of engineered fill. For bidding purposes please clarify depth of engineered fill required under footings and slab?			
	108	1/26/2026	Technical	The architectural plans call out some steel studs in the apartment units. Please clarify all wood stud framing will be acceptable?			

	109	1/26/2026	Technical	Survey & Control Responsibility The civil sheets reference NAD83(2011) State Plane South and RTK control points CPT 100–103. Please confirm whether the Contractor is required to establish new primary control points or may rely solely on the CPT points shown. Additionally, clarify whether an independent as-built survey is required at project closeout.			
	110	1/26/2026	Technical	Permitting Authority Please confirm which agency holds authority for: •Stormwater/NPDES permitting •Utility tie-in approvals •Traffic control approvals along Antelope Dr. and Cougar St. Also confirm whether IHS will obtain these permits or if the Contractor is responsible.			
	111	1/26/2026	Technical	Underground Utility Verification Multiple existing sanitary manholes, storm structures, and water lines are shown on Sheets C001, C300. Will IHS provide a subsurface utility engineering (SUE) report, or is the Contractor responsible for potholing and verification prior to excavation?			
	112	1/26/2026	Technical	Retaining Wall Design Criteria Sheet C404 shows multiple retaining walls with bottom wall elevations and swales. Please confirm if the retaining wall design is performance-based or prescriptive. Are stamped structural calculations required from the Contractor?			
	113	1/26/2026	Technical	Drywell Performance Requirements Sheet C505 details drywell construction. Please confirm the required infiltration rate and whether field percolation testing is required prior to installation			
	114	1/26/2026	Technical	Maintenance Responsibility Please clarify whether long-term inspection and maintenance of drywells and Nyoplast inlets will be the responsibility of IHS or the Contractor during warranty period.			
	115	1/26/2026	Technical	Fire Flow Requirements Please provide minimum required fire flow and residual pressure requirements for the site to validate the sizing of the 6" DIP fire/domestic water line.			
	116	1/26/2026	Technical	Sanitary Sewer Capacity Please confirm that the existing sanitary system has sufficient capacity for the new multiplex loading and provide available flow data if applicable			
	117	1/26/2026	Technical	Light Pole Foundations Please confirm whether light pole base design is prescriptive or if the Contractor must submit engineered foundation designs for approval.			
	118	1/26/2026	Technical	Transformer Installation A proposed transformer is shown on Sheet C200. Please confirm whether the utility provider or Contractor is responsible for transformer procurement, pad construction, and final electrical connections.			
	119	1/26/2026	Technical	Traffic Control Plan Please confirm whether a site-specific traffic control plan is required for work along Antelope Dr. and Cougar St., and if so, whether IHS will provide a standard or Contractor must submit engineered plans.			
	120	1/26/2026	Technical	As-Built Deliverables Please confirm format requirements for record drawings (PDF, CAD, GIS-compatible) and whether utility locations must be GPS-verified.			
	121	1/26/2026	Technical	Key Personnel Commitment Section H.6 identifies Project Manager, Superintendent, and Safety Officer as Key Personnel. Are these personnel required to be dedicated full-time to this project? Can one person fulfill multiple positions if qualified?			
	122	1/26/2026	Technical	Delegated Design Scope Sections 013300 and 014000 require sealed design for Contractor-designed systems. Please identify all systems requiring delegated design (e.g., trusses, retaining walls, light pole foundations, fire sprinkler design, HVAC supports, site shoring).			
	123	1/26/2026	Technical	Environmental Manager Authority Section 013100 requires a Contractor Environmental Manager. Please confirm whether this role must be full-time on-site and whether environmental training certifications must be submitted for approval.RFI-013 — Permitting Jurisdiction			
	124	1/26/2026	Technical	Permitting Jurisdiction Section 013100 states Contractor is responsible for all permits. Please identify all expected permitting authorities (Tribal, Federal, State, Local) and clarify whether any permits will be Government-furnished.			

	125	1/26/2026	Technical	Systems Requiring Sealed Engineering Multiple sections (e.g., 211313 Wet-Pipe Sprinklers, 230800 HVAC Commissioning, 260010 Electrical Supplemental) reference delegated design and engineered submittals. Please provide a definitive list of all systems that require Contractor-provided, PE-sealed design (sprinkler hydraulics, HVAC controls, electrical distribution, site utilities, structural supports, shoring, equipment pads, etc.).			
	126	1/26/2026	Technical	AHJ Approval Authority Please identify the Authority Having Jurisdiction (AHJ) for sprinkler system approval (IHS Fire Protection Engineer, Tribal Fire Marshal, State Fire Marshal, or Local Fire Department).			
	127	1/26/2026	Technical	The project documents state a Geotech Report would be attached but we cannot locate it. Would you please release this document?			
	128	1/26/2026	Technical	Who will be the AHJ? Does the IHS have authority over local and/or state inspectors?			
	129	1/26/2026	Technical	Will the contractor need to pull any permits, such as a building permit or utility tap permits?			
	130	1/26/2026	Technical	Can a qualified superintendent also act as the site safety officer, or is this expected to be 2 separate on-site individuals?			
A0002	131	1/26/2026	Admin	Can the site visit attendance list be provided?	01/27/2026	It is being provided by Amendment A0002.	IHS CS
	132	1/26/2026	Technical	Section H.42 of the Solicitation requires a physical barrier between the construction zone and hospital/clinic operations. As this site is a block from the hospital, what shall the contractor anticipate for an approved barrier? Is a temporary chain link fence acceptable?			
	133	1/26/2026	Technical	Are there any owner furnished items, appliances, equipment?			
	134	1/26/2026	Technical	Can the definition of "relevant" for past projects in Factor 1 Specialized Experience be expanded to new construction or major remodels that contain multiple scopes and similar in complexity?			
	135	1/26/2026	Technical	In Factor 2: Example Construction Schedule and Narrative it requests a clear understanding of the numerous requirements of a healthcare construction project. Given that this is more of a residential project rather than a healthcare facility, can our example schedule be from a project of a similar complexity and not restricted to a healthcare project?			
	136	1/26/2026	Technical	Wall type C detail on A111 has wood studs w/ sound batt noted at the top, and metal studs with no sound batt indicated towards the bottom. The drawing resembles the same wall from floor to ceiling. Please explain.			
	137	1/26/2026	Technical	Can wood studs be substituted for any area shown to receive metal studs?			
	138	1/26/2026	Technical	Is the entire attic to receive closed cell spray foam insulation R-60? If not, can you provide clarity on the extent? Also, there doesn't appear to be a specification provided for this product.			
	139	1/26/2026	Technical	Typical foundation details on sheet S501 show top of footing at 3' below grade, and roughly 2'6" below grade at brick ledges. It is typical for footings to be minimum 4' below grade in other parts of South Dakota. Does the current foundation design meet code for frost protection in this geographical region?			
	140	1/26/2026	Technical	Spec 092900 Gypsum Board Finish Levels says Level 3 where indicated on drawings. Are some areas acceptable at a Level 3? If so, please indicate where.			
	141	1/26/2026	Technical	Is the drywall finish to be smooth, or is texture acceptable?			
	142	1/27/2026	Technical	We have been working with NPPD and sent them all the information on the project. They will not guarantee that they will have their cost or what their plan is to get power to the site till after the bid date. In the past we have done an allowance to include or let IHS pay this direct. Please advise			
	143	1/27/2026	Technical	We do not see that there is any communication service to the building for internet/ phone or TV. Please clarify if this is required.			

	144	1/27/2026	Technical	There are no fire alarm devices shown in the building other than power to the annunciator. Please clarify what is required.			
	145	1/27/2026	Technical	Is the contractor responsible for surveying and staking of the building and utilities?			
	146	1/27/2026	Technical	Is the contractor responsible for testing? Density testing, concrete testing and other?			
The Government is still working on the pending responses and will not accept any further questions or inquiries concerning this RFP.							